

LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

FOR CORNERS OF--:	LOCATED IN--:	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY _____ T. <u>21</u> N. <u>●</u> R. <u>16</u> W. <u>●</u>		E-7; F-7; G-7; G-9
2. PROPERTY CONTROLLING IN SECTION _____ T. _____ N. _____ S. _____ R. _____ E. _____ W. _____		
3. MISCELLANEOUS PROPERTY IN SECTION _____ T. _____ N. _____ S. _____ R. _____ E. _____ W. _____		
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, Carl F. Roser, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were, in a field survey on October 28, 19 , established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on _____, 19 , found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

~~A. Description of original monument and accessories and/or subsequent restoration:~~

C. (continued)

G-9

Fd. FS conc. mon. in ctr. rds. E-W & N			
24" B.Oak	N25°W	85.22	
5" W. Pine	S17°E	91.18	
6" W. Oak	S50°W	101.66	

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

- E-7 Found 3/8" cabin spike in b'top road over strong mag. pull that fits witness & survey data, reasonable, by previous surveys by R.L.S.'s Dodt, Stephens & Slawinski.
- F-7 Found iron w/R.L.S. cap that fits two witness remains (stumps) by R.L.S. K. Stephens and Section 21 subdivision by R.L.S. T. Slawinski.
- G-7 Fd. 3/8" cabin spike in b'top over strong dip that fits witnesses by Stephens, Ross, and co. rd. comm. Corner also used by Slawinski & Dodt. Note: position for corner from two G. Johnson witnesses would be S85°E, 13'±.
- G-9 Fd. U.S.F.S. concrete monument which was a perpetuation of corner by R.L.S. Stephens.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

E-7	F-7	G-7
Fd. 3/8" spike in b'top rd. over strong mag. pull 10" Oak N37°E 67.55 12" Oak S35°E 43.48	Fd. RLS cap on iron ref. rod/RLS cap 13" Oak S02°W 33.00 12" Oak S15°W 37.00 11" Oak N42°W 94.68 11" Oak N05°E 77.34 Ctr. E-W b'top rd. Due S 1'±	3/8" spk. in b'top road over strong mag. pull 13" B.Oak N13°W 46.97 8" B.Oak N30°E 50.20 Power Pole S30°W 30.92 Ctr. E-W b'top rd. Due N 1'± Ctr. sand rd. to S Due E 20'±

SIGNED BY Carl F. Roser 9-15-76 DATE _____

SURVEYOR'S MICHIGAN REGISTRATION NO. 12028


FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY _____ DATE _____

CHIEF OF SURVEY PARTY

APPROVED AND SIGNED BY _____ DATE _____

MICHIGAN REGISTERED LAND SURVEYOR



(SEAL)

SURVEYOR'S MICHIGAN REGISTRATION NO. _____

STRONACH TOWNSHIP
MANISTEE COUNTY