

# LAND CORNER RECORDATION CERTIFICATE

## FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

FOR CORNERS OF--	LOCATED IN--	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY	T. 21 N. R. 16 W.	H-7; I-7
2. PROPERTY CONTROLLING IN SECTION 22	T. 21 N. R. 16 W.	9; 11
3. MISCELLANEOUS PROPERTY IN SECTION	T. S. R. E. W.	
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, Carl F. Roser, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were, in a field survey on October 28, 1975, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on \_\_\_\_\_, 19\_\_\_\_, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. Description of original monument and accessories and/or subsequent restoration:

C. (continued)

11  
Set 1 1/4"x36" pipe & cedar post  
w/loc. tag  
Cedar N60°W 13.0  
Cedar N30°E 4.3  
Cedar S45°E 8.0  
N-S fence remains Due E 55±3'

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

- H-7 Reestablished 1/4 corner equidistant & on line between section corners to E & W.
- I-7 Found 2" pipe that fits three witnesses as noted in item "C" by R.L.S. Ken Ross.
- 9 Established NW corner NE 1/4-SE 1/4 of Sec. 22; equidistant & on line between center of section to W and 1/4 corner to E.
- 11 Established the center of SW 1/4 of Sec. 22 per standard B.L.M. instructions.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

H-7	I-7	9
Set DNR mon. & cedar post	Fd. & accepted 2" pipe buried	Set 1 1/4"x3' pipe & cedar pipe
<del>8" W. Oak N15°W 3.2</del>	in E-W road	w/loc. tag
<del>11" W. Oak S55°E 30.8</del>	5" W. Pine Due N 45.98	4" W. Pine S60°W 10.3
<del>11" B. Oak N85°W 10.3</del>	16" B. Oak N50°E 34.72	3" W. Pine N65°W 8.9
E-W Dirt Road Due N 29	22" B. Oak S15°E 20.97	3" W. Pine N70°E 4.3
10" W. OAK N35E 3.7'		
12" W. OAK S60E 33.6'		
12" B. OAK N85W 7.0'		

SIGNED BY Carl F. Roser 9-15-76 DATE \_\_\_\_\_

SURVEYOR'S MICHIGAN REGISTRATION NO. 12028


FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY \_\_\_\_\_ DATE \_\_\_\_\_

CHIEF OF SURVEY PARTY

APPROVED AND SIGNED BY \_\_\_\_\_ DATE \_\_\_\_\_

MICHIGAN REGISTERED LAND SURVEYOR



(SEAL)

SURVEYOR'S MICHIGAN REGISTRATION NO. \_\_\_\_\_ STRONACH TOWNSHIP  
MANISTEE COUNTY