

SECTION

LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

Manistee Located In: Corner Code #  
 (County)

1. Public Land Survey T 21N R 17W M-09  
 T \_\_\_ R \_\_\_ SE Sec. Cor  
 T \_\_\_ R \_\_\_ Sec. 24  
 T 21N R 16W (A9 E-File)

2. Property Controlling S \_\_\_ T \_\_\_ R \_\_\_  
 in Section S \_\_\_ T \_\_\_ R \_\_\_

3. Miscellaneous S \_\_\_ T \_\_\_ R \_\_\_  
 Property in Sec. S \_\_\_ T \_\_\_ R \_\_\_

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_

5. Private Claims \_\_\_\_\_

REGISTER'S OFFICE  
MANISTEE COUNTY

98-344 at 9:25am  
JUN 29 1998

Deborah Six  
REGISTER OF DEEDS

Register of Deeds Stamp & File Number

I, Anthony M. Slawinski, in a field survey on May 27, 19 98 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

- Set by John Brink in 1839
1. Hemlock 10" S 67° W 20 links (Gone)
  2. Yellow Pine 12" N 34½° W 20 links (Gone)

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Information Referenced:

- Willowville Plat, Recorded on April 24, 1950 in Liber 3B of Plats, page 57 Survey certificate by Slawinski (1968)  
 Survey Notes by Slawinski (1968)
- Michigan Department of Transportation Map (1952) Found Iron Survey Certificate by Weinert
3. N 52° W 55.11' 21" Oak (Gone)
  4. N 28° E 80.52' 16" Pine (Gone)
  5. N 59° E 70.85' 20" Oak (Gone)
- Survey Certificate by Slawinski (1985)

Survey Certificate by Vaillencourt (1961)

On May 27, 1998, I, Anthony Slawinski, along with Abonmarche, found a 1" iron rod within a monument box, ± 9 feet West of Centerline of Highway U.S.-31.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

On May 27, 1998, I installed a Manistee County Monument, within a monument box, in the exact location as the above mentioned 1" iron pipe, as a careful and faithful re-establishment of the position of the original corner, and witnessed by:

6. N 45° W 71.71' Power Pole, 16D nail and tag in SW side
7. N 50° E 70.19' Power Pole, 16D nail and tag in SE side
8. S 66° E 85.40' Power Pole, 16D nail and tag in NE side
9. S 55° W 146.73' 5" Red Pine, 60D spike in SE side

Note: Corner is located ±9 feet West of Centerline of Highway U.S.-31.  
 North 2657.48' to East ¼ Corner of Section 24, T21N, R17W.  
 West 2683.51' to South ¼ Corner of Section 24, T21N, R17W.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6			5		4		3		2			1
3													
4	7			8		9		10		11			12
5													
6	18			17		16		15		14			13
7													
8	19			20		21		22		23			24
9													
10	30			29		28		27		26			25
11													
12	31			32		33		34		35			36
13													

Comer M-09  
 ratified by the Manistee County Peer Group according to the county plan adopted pursuant to P.A. 345 of 1990, as amended, (being the State Survey and Remonument Act, MCL 54.261 et. seq.). Date of Peer Review: JUN 2 1998  
 Anthony M. Slawinski



Signed by Anthony M. Slawinski  
 Surveyor's Michigan License No. 13597

Date 6-1-98