

LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

MANISTEE
(County)

Located In:

Corner Code #

- | | | | | | |
|-------------------------------------|---|-----|---|-----|------|
| 1. Public Land Survey | T | 21N | R | 16W | E-13 |
| | T | | R | | |
| | T | | R | | |
| | T | | R | | |
| 2. Property Controlling in Section | S | | T | R | |
| | S | | T | R | |
| 3. Miscellaneous S Property in Sec. | T | | R | | |
| | S | | T | R | |

**REGISTER'S OFFICE
MANISTEE COUNTY**

98-258 at 4:05pm
JUL 01 1998

Regina Dix
REGISTER OF DEEDS

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

| | A | B | C | D | E | F | G | H | I | J | K | L | M |
|----|----|----|----|----|----|----|---|---|---|---|---|---|---|
| 1 | | | | | | | | | | | | | |
| 2 | 6 | 5 | 4 | 3 | 2 | 1 | | | | | | | |
| 3 | | | | | | | | | | | | | |
| 4 | 7 | 8 | 9 | 10 | 11 | 12 | | | | | | | |
| 5 | | | | | | | | | | | | | |
| 6 | 18 | 17 | 16 | 15 | 14 | 13 | | | | | | | |
| 7 | | | | | | | | | | | | | |
| 8 | 19 | 20 | 21 | 22 | 23 | 24 | | | | | | | |
| 9 | | | | | | | | | | | | | |
| 10 | 30 | 29 | 28 | 27 | 26 | 25 | | | | | | | |
| 11 | | | | | | | | | | | | | |
| 12 | 31 | 32 | 33 | 34 | 35 | 36 | | | | | | | |
| 13 | | | | | | | | | | | | | |

I, Richard L. Hays, in a field survey on April 1998, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

SOUTHEAST CORNER OF SECTION 32, T21N-R16W
1838: G.L.O. Survey by John Brink Set Post
10" W. Pine N-77°-E 54 Lks (1)
14" W. Oak N-57°-W 10 Lks (2)

1971: Robert Griffin L.C.R.C. 73-27 Found Iron Pin
10" White Pine S-54°-E 119.77' (3)
8" White Oak S-33°-E 80.39' (4)
10" White Pine S-78°-W 60.39' (5)
4X7 Post West 32.98' (6)
6" Red Oak N-50°-W 63.12' (7)
NE Cor. of Section 6, T20N-R16W S-86°-49'-45"-E 1156.90' (8)

Undated Site Map of the C.C.C. Camp
Iron Pin in Monument at the Intersection
of North and East Roads
No Witnesses

1990: Stanley H. Shackelford 4-28-1990 L.C.R.C. 90-177
10" White Pine S-54°-E 119.77' (3)
8" White Oak S-33°-E 80.39' (4)
10" White Pine S-78°-W 60.39' (5)
4X7 Post West 32.98' (6)

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

SOUTHEAST CORNER OF SECTION 32, T21N-R16W

APRIL 1998: Found 1" Pipe over U.S.F.S. Monument set in 1974 in Centerline of Camp Rd and Old Trail. Condition of the witnesses are as follows:

| | | | |
|----------------|---------|-------------|-------|
| 10" W. Pine | N-77°-E | 54 Lks (1) | GONE |
| 14" W. Oak | N-57°-W | 10 Lks (2) | GONE |
| 10" White Pine | S-54°-E | 119.77' (3) | FOUND |
| 8" White Oak | S-33°-E | 80.39' (4) | FOUND |
| 10" White Pine | S-78°-W | 60.39' (5) | FOUND |
| 4X7 Post | West | 32.98' (6) | GONE |
| 6" Red Oak | N-50°-W | 63.12' (7) | FOUND |

NE Cor. of Section 6, T20N-R16W S-86°-49'-45"-E 1156.90' (8) DID NOT CHECK

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

SOUTHEAST CORNER OF SECTION 34, T21N-R16W

APRIL 1998: Accepted U.S.F.S. Monument as the best available evidence of the position of the Corner.

| | | | |
|----------------|---------|------------|----------------|
| 11" White Oak | S-33°-E | 80.39' (4) | 10" Dock Spike |
| 12" Red Oak | N-50°-W | 63.12' (7) | 10" Dock Spike |
| 17" White Pine | S-78°-W | 60.86' (5) | 10" Dock Spike |
| 10" White Oak | S-30°-W | 62.71' | 60 Penny Spike |
| 20" White Pine | N-64°-E | 45.95' | 60 Penny Spike |

Corner E-13

ratified by the Manistee County Peer Group

according to the county plan adopted pursuant to P.A. 345 of 1970 as amended, (being the State Survey and Remonument Act, MCL 207.1 et. seq.). Date of Peer Review: MAY 5 1998

Signed by Richard L. Hays Date May 1, 1998
Anthony M. Slawski

Surveyor's Michigan License No. 25847

