

**SURVEY & REMONUMENTATION**

**SURVEY & REMONUMENTATION**

**APR 28 1998**

**LAND CORNER RECORDATION CERTIFICATE**

**JAN 21 1998**

**Filing Requirement of Act 74, Mich. P.A. 1970**

For corners in SECTION Located In: Corner Code #

Manistee (County)

1. Public Land Survey T 21N R 16W G-13  
 T \_\_\_\_\_ R \_\_\_\_\_  
 T \_\_\_\_\_ R \_\_\_\_\_  
 T \_\_\_\_\_ R \_\_\_\_\_

2. Property Controlling S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_  
 in Section S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_

3. Miscellaneous S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_  
 Property in Sec. S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_

**SECTION**  
**REGISTER'S OFFICE**  
**MANISTEE COUNTY**  
 97-183 at 4:30pm  
**JUN 10 1997**  
*Deborah Six*  
**REGISTER OF DEEDS**

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
 5. Private Claims \_\_\_\_\_

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, Richard L. Hays, in a field survey on April 1997, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

**A. Description of original monument and accessories and/or subsequent restoration:**

G-13 SOUTHEAST CORNER OF SECTION 33, T21N-R16W  
 1837: G.L.O Post  
 14" White Oak N-53½°-E 47 lks (1)  
 10" Yellow Pine N-75°-W 65 lks (2)  
 UNDATED: Pere Marquette Railroad Map  
 Southwest Corner of Section 34 is 380.75'  
 West of Station 930+72 (3)

1972: Robert Griffin #13584, LCRC #73-29  
 Set Corner at Proportionate Distance between Controlling Corners.  
 8" Red Oak N-16°-E 20.32' (4)  
 4" Pine Post West 1.3' (5)  
 7" Black Oak N-59°-W 55.70' (6)  
 6" White Oak N-77°-W 31.42' (7)  
 The Railroad Map does not fit the Known Corners and Lines in this Township and is therefore of little value.

**B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:**

G-13 SOUTHEAST CORNER OF SECTION 33, T21N-R16W  
 April 1997: Found a 5" Square Concrete Monument, 5' in length with a 3" Stamped Brass Disc, 1.5' above the ground.

Condition of the Witnesses are as follows:

14" White Oak	N-53½°-E	47 lks (1)	GONE
10" Yellow Pine	N-75°-W	65 lks (2)	GONE
SW Section Corner	West 380.75' of Station 930+72	(3)	GONE
8" Red Oak	N-16°-E	20.32' (4)	FOUND
4" Pine Post	West	1.3' (5)	GONE
7" Black Oak	N-59°-W	55.70' (6)	FOUND
6" White Oak	N-77°-W	31.42' (7)	FOUND

Corner G-13 ratified by the Manistee County Peer Group according to the county plan adopted pursuant to P.A. 345 of 1990, as amended, (being the State Survey and Remonument Act, MCL 54.261 et. seq.). Date of Peer Review: JUN 3 1997

**C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:**

G-13 SOUTHEAST CORNER OF SECTION 33, T21N-R16W

April 1997: Accepted the 5" Square Concrete Monument, 5' in length with a 3" Stamped Brass Disc as a careful and faithful re-establishment of the position of the Original Corner.

10" Red Oak	N-16°-E	20.47' (4)
9" Black Oak	N-59°-W	55.70' (6)
8" White Oak	N-77°-E	31.42' (7)
8" White Oak	N-32°-W	44.88'

Corner is 215' South of the Centerline of the County Line Road.  
 Corner is 340' West of the Centerline of the Railroad



Signed by Richard Hays

Date 5/29/97

Surveyor's Michigan License No. 25847