

LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. P.A. 1970

**REGISTER'S OFFICE
MANISTEE COUNTY**

#95-388 AT 1:27 p.m.

OCT 09 1995

Penny A. Pepera
REGISTER OF DEEDS

Register of Deeds Stamp & File Number

For corners in

Manistee

(County)

Located In:

Corner Code ##

- | | | |
|------------------------------------|---------------------------|------------|
| 1. Public Land Survey | T <u>21N</u> R <u>16W</u> | <u>H-7</u> |
| | T _____ R _____ | _____ |
| | T _____ R _____ | _____ |
| | T _____ R _____ | _____ |
| 2. Property Controlling in Section | S _____ T _____ R _____ | _____ |
| | S _____ T _____ R _____ | _____ |
| 3. Miscellaneous Property in Sec. | S _____ T _____ R _____ | _____ |
| | S _____ T _____ R _____ | _____ |

4. Lot No. _____, Recorded Plat _____

5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, Richard Hays, in a field survey on June, 1995

do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

H-7 QUARTER CORNER COMMON TO SECTIONS 15 & 22
 1847:G.L.O. Survey 1976:Carl Roser
 11" W. Oak N-67 1/2-W 20 Lks Re-established corner, equal distance
 10" W. Oak S-50°-W 29 Lks and on line between Section Corners
 and set D.N.R. Monument:
 1915:E.W. Meuscher Book A, pg 64 10" W. Oak N-35°-W 3.7'
 6" B. Oak N-82 1/2-W 61 1/3' 12" W. Oak S-60°-E 33.6'
 5" W. Oak S-71 3/8-E 60 1/2' 12" B. Oak N-85°-W 7.0'
 Centerline E&W Road North 29'

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

H-7 QUARTER CORNER COMMON TO SECTIONS 15 & 22
 1995:Found D.N.R. Monument and Witnesses:
 10" W. Oak N-35°-W 3.7'
 12" B. Oak N-85°-W 7.0'
 Centerline E&W Road North 29'


Corner H-07 ratified by the Manistee County Peer Group according to the county plan adopted pursuant to P.A. 345 of 1990, as amended, (being the State Survey and Monument Act, MCL 54.261 et. seq.). Date of Peer Review: [Signature]

JUL 5 1995

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

H-7 QUARTER CORNER COMMON TO SECTIONS 15 & 22
 1995:Accepted D.N.R. Monument as a careful and faithful reestablishment of the position of the Original Corner.
 18" B. Oak N-85°-W 7.50'
 12" W. Oak N-35°-E 4.22'
 8" R. Pine S-17°-E 63.27'
 10" W. Oak N-03°-E 79.45'
 Centerline E&W Road North 29'

Signed by Richard Hays



Date July 5, 1995

Surveyor's Michigan License No. 25847