

same as A-7  
T21N, R15W

SECTION

**LAND CORNER RECORDATION CERTIFICATE**  
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

<u>Manistee</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T <u>21N</u> R <u>16W</u>	<u>M-7</u> ✓
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

REGISTER'S OFFICE  
MANISTEE COUNTY  
#95-392 AT 1:37 p.m.  
OCT 09 1995  
Penny A. Peoples  
REGISTER OF DEEDS

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

A	B	C	D	E	F	G	H	I	J	K	L	N
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

I, Richard Hays, in a field survey on June, 19 95, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the cornerpoints mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

A. Description of original monument and accessories and/or subsequent restoration:

**M-7 SECTION CORNER COMMON TO SECTIONS 13 & 24, T21N, R16W & 18 & 19, T21N, R15W**  
1847:G.L.O. Survey 1973:Kenneth Ross  
24" W. Pine S-25°-E 43 Lks Act 74 #73-20 Found Walker  
10" W. Oak N-84 1/2-W 43 Lks Monument.  
16" B. Oak N-10°-W 46.95'  
1908:D. Skeels, Book B 246 16" W. Oak N-25°-W 56.15'  
24" W. Pine Stmp N-17°-E 63 Lks 24" B. Oak S-80°-E 57.89'  
8" Y. Pine S-27°-E 20 Lks Centerline of Road West 21.4'

1946 TO 1950: Concrete Monument set by Sam Walker  
B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

**M-7 SECTION CORNER COMMON TO SECTIONS 13 & 24, T21N, R16W & 18 & 19, T21N, R15W**  
1995: Found Stainless Steel Rivet in Concrete in 3" Pipe set by Sam Walker and Ross Witnesses:

16" B. Oak N-10°-W 46.95'  
16" W. Oak N-25°-W 56.15'  
24" B. Oak S-80°-E 57.89'  
Centerline of Road West 21.4'

Corner M-07 ratified by the Manistee County Peer Group according to the county plan adopted pursuant to P.A. 345 of 1990, as amended, (being the State Survey and Remonument Act, MCL 54.261 et. seq.). Date of Peer Review: Richard A. Hays

JUL 5 1995

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

**M-7 SECTION CORNER COMMON TO SECTIONS 13 & 24, T21N, R16W & 18 & 19, T21N, R15W**  
1995: Accepted Stainless Steel Rivet in concrete in a 3" pipe set by Sam Walker as the best available evidence of the position of the Original Corner. Set two Irons by the Monument.

24" B. Oak S-80°-E 58.10'  
15" B. Oak S-05°-W 29.64'  
8" B Oak S-56°-W 79.84'  
18" B Oak N-10°-W 39.54'  
Wood Post West 1.00'  
Centerline of Dirt Road West 21.5'



Signed by Richard Hays  
Surveyor's Michigan License No. 25847

Date July 5 1995