

SECTION

LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. P.A. 1970

For corners in MANISTEE (County)

Located In:

Corner Code #

1. Public Land Survey

T 21 NR 16 W
T 21 NR 15 W

M-8
A-8

2. Property Controlling in Section

S T R
S T R

3. Miscellaneous Property in Sec.

S T R
S T R

4. Lot No. Recorded Plat
5. Private Claims

REGISTER'S OFFICE
MANISTEE COUNTY

97-402 at 4:05pm
OCT 24 1997

Reborah Six
REGISTER OF DEEDS

Register of Deeds Stamp & File Number

I, Sammy S. Barnett, in a field survey on August 22nd 1997, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

Grid table with columns A-LM and rows 1-13. Contains numbers 1-36 in a grid pattern.

A. Description of original monument and accessories and/or subsequent restoration:

M - 8 1/4 corner common to section 24 T21N R16W & section 19 T21N R15W

1837 GLO survey by John Brink
Monument - Post
1 W. Pine 16" S181/2W 55 lks (36.3')
2 W. Oak 10" N841/2W 43 lks (28.38')

1949 Sam Walker Iron set
370' S. of intersection of roads N - SE & NW
no other witnesses

1938 by R.D. Lyons
Found Oak stake rotted into ground
agrees with Manistee Co. record atlas
3 B. Oak 13" N25E 54 lks (35.64')
4 W. Oak 9" S66E 21 lks (13.86')

1973 K. Ross # 17634 found 1" pipe
7' E. of W. edge pine planting
5 W. Pine 6" S15W 5.68'
6 B. Oak 20" West 32.93'
7 B. Oak 8" N60W 25.83'

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

M - 8 1/4 corner common to section 24 T21N R16W & section 19 T21N R15W

On August 22nd 1997, I found the 1" pipe from the Ross witnesses.
Condition of the witnesses are as follows,

1 Gone # 2 Gone # 3 Found stump NE 35'+ - # 4 Found stump SE 14' + - # 5 Found # 6 Found stump # 7 Found.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

M - 8 1/4 corner common to section 24 T21N R16W & section 19 T21N R15W

On August 22nd 1997, I replaced, in the exact location, the 1" pipe with a Manistee County Monument, and accepted this location as a careful and faithful perpetuation of the original corner, and took the following witnesses.

8 W. Pine 10" S26W 5.65' existing 60d spike in East side (# 5)
9 B. Oak 10" N46W 25.91' existing 60d spike in Northeast side (# 7)
10 W. Pine 8" N42E 16.55' placed a 60d spike in Southeast side
11 W. Pine 8" S41E 29.95' placed a 60d spike in Northeast side
Old pine post 1' West

Corner is approximately 370' South of road Nine Mile Bridge Road
Corner is set flush with ground surface

Signed by Sammy S. Barnett Date 10-17-97

Surveyor's Michigan License No. P S # 16923



Corner M-08 ratified by the Manistee County Peer Group
according to the county plan adopted pursuant to P.A. 345 of 1990,
and recorded, (being the State Survey and Remonument Act, MCL 56261
et. seq.). Date of Peer Review OCT 7 1997