

LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, MICH. P.A. 1970

APR 03 1996

ALSO
 A-10 T21N
 R13W

FOR CORNERS OF--:	LOCATED IN--:	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY _____ T. <u>21N</u> N. <u>14W</u> E. _____ S., R. _____ W.		M-10
2. PROPERTY CONTROLLING IN SECTION _____, T. <u>21N</u> N. _____ S., R. <u>13W</u> E. _____ W.		(A-10) ✓
3. MISCELLANEOUS PROPERTY IN SECTION _____, T. _____ N. _____ S., R. _____ E. _____ W.		
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER'S OFFICE
 MANISTEE COUNTY
 #93-212 AT 11:32 A.M.
APR 20 1993
Annika P. Papp
 REGISTER OF DEEDS

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, Patrick R. Leemon do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above (identified with circles on index code diagram - over) were, in a field survey on January 23 1993, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on _____ 19____, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. Description of original monument and accessories and/or subsequent restoration:

1/4 corner common to section 25 of T21N R14W and Section 30 of T21N R13W
 1963 Survey by Robert A. Griffin
 Monu. Set 5" sq. by 60" long concrete monu. with 3" brass disk.
 Witnesses
 W.Oak 15 N82.5E 36.85'
 W.Oak 5 S31E 77.15'
 R.Pine 3 N67W 153.90'
 Cedar Post 5 South 1.6'

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

I found the monument and all the witnesses to be in good condition.
 The monument extends 1.4' above the surface.
 Liber 73 Page 150 documents the history of this corner as perpetuated by Griffin.

Corner M-10 ratified by the Manistee County Peer Group pursuant to P.A. 123 of 1915, as amended by P.A. 195 of 1990, as amended. Date of Peer Review: FEB 1 1993

C. Description of monument for corner and accessories established to perpetuate locating the position of corner:

1/4 corner common to section 25 of T21N R14W and Section 30 of T21N R13W
 Monu. 5" sq. by 60" long concrete monu. with 3" brass disk.
 Witnesses
 W.Oak 15 N82.5E 36.85'
 W.Oak 5 S31E 77.15'
 R.Pine 7 N67W 153.90'
 Cedar Post 5 South 1.6'
 W.Oak 11 S52E 75.39'
 R.Oak 7 N39E 65.30'
 CL of N-S Powerline is East 8'


SIGNED BY Patrick R. Leemon DATE January 25, 1993

SURVEYOR'S MICHIGAN REGISTRATION NO. 31595

FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY _____ DATE _____
CHIEF OF SURVEY PARTY

APPROVED AND SIGNED BY _____ DATE _____
MICHIGAN REGISTERED LAND SURVEYOR



SURVEYOR'S MICHIGAN REGISTRATION NO. _____