

DEC 28 1998

LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. P.A. 1970

SECTION

For corners in Manistee Located In: _____ Corner Code # _____
 (County)

1. Public Land Survey T 21N R 13W M-07
 T _____ R _____
 T _____ R _____
 T _____ R _____

2. Property Controlling in section S _____ T _____ R _____
 S _____ T _____ R _____

3. Miscellaneous Property in Sec. S _____ T _____ R _____
 S _____ T _____ R _____

REGISTER'S OFFICE
 MANISTEE COUNTY
 98-278 at 3:30pm
 JUL 07 1998
Deborah Dix
 REGISTER OF DEEDS

Register of Deeds Stamp & File Number

4. Lot No. _____ Recorded Plat _____
 5. Private Claims _____

I, Kenneth L. Ross, in a field survey on June 8 1998, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, re-monumented, recovered, found as expressed below.

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

A. Description of original monument and accessories and/or subsequent restoration:
 M-07 Section Corner for Sections 13 & 24, T21N-R13W.

1839, John Brink, G.L.O., Boundary Survey
 Set Wood Post
 #1 White Pine 10" S 60.5 W 33 lks. (21.78')
 #2 Yellow Pine 12" N 66.5 W 23 lks. (15.18')

1909, Fargo Eng. Co. (Book "A", Page 8)
 monument not given, but found both Gov't witnesses well preserved.
 #3 White Pine Stump N 27 E 26.75 lks. (17.65')

New witness were taken. (Liber 1, Page 432)
 #4 White Oak 8" N 60 W 47.72' (scrub. BT 23)
 #5 Black Oak 10" S 54 W 18.47' (scrub. BT 24)
 #6 Black Oak 10" N 65 E 22.35' (scrub. BT 18)
 #7 White Oak 6" S 44 E 60.33' (scrub. BT 19)

1959, George Blass, RLS # 5489
 Blass does an extensive search of area to locate Fargo corner, (Iron Pipe & Crookery), he believes it's been removed threw plowing and planting, but finds Fargo's witness, W. Pine Stp., from recorded distance & bearing found traces of lime in soil, a practice use by Fargo Eng. in this area. Set a 6" dia. by 5' conc. monument, with a 3-1/2" brass cap, stamp to identify the corner.

1979, Clint Cole, RLS# 17613
 Used Blass monument in Survey
 Recorded witness's #5, #6 and #7
 (Liber 1, Page 601)

1992, Norm Caldwell, RLS# 12018
 Used Blass monument in
 Cadastral Survey for U.S.F.
 Recorded witness's #4, #5,
 #6 and #7. (Liber 76, Page 30)

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
 M-07 Section Corner for Sections 13 & 24, T21N-R13W.

On June 8, 1998, I found 6" round concrete monument placed by Blass, monument sets one foot above the ground and 35 feet East of USFS road. I found no evidence to dispute this location for the corner.


Condition of record witnesses are as follows; #1 Gone #2 Gone #3 Found remains of stump
 #4 Gone #5 Found in good condition #6 Found in good condition
 #7 Found in good condition

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
 M-07 Section Corner for Sections 13 & 24, T21N-R13W.

I accepted Blass's 5" round by 5' long concrete monument, with 3 1/2" brass cap, stamped to identify the corner as a substantial marker for the corner and is accepted as a careful and faithful perpetuation of the position of the original corner.

Ext."BT" White Oak twin 11"-18" N 89 W 67.60' (dock spk. in SW side of tree)
 Ext."BT" #5 Black Oak 14" S 54 W 18.83' (set 60d spike in NW side of tree)
 Ext."BT" #6 Black Oak 12" N 65 E 22.47' (set 60d spike in NW side of tree)
 Ext."BT" #7 White oak 10" S 44 E 60.48' (set 60d spike in NE side of tree)

ratified by the Manistee County Peer Group according to the county plan adopted pursuant to P.A. 345 of 1990, as amended, (being the State Survey and Remonument Act, MCL 54-261 et. seq.). Date of Peer Review: JUL 7 1998
Auth. n. 11



Signed by *Kenneth L. Ross* Date July 2, 1998

Surveyor's Michigan License No. 17634