

MAY 16 1997

COMMISSION

LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. P.A. 1970

For corners in MANISTEE Located In: \_\_\_\_\_ Corner Code # \_\_\_\_\_  
 (County)

1. Public Land Survey T 21N R 13W M-9  
 T \_\_\_\_\_ R \_\_\_\_\_  
 T \_\_\_\_\_ R \_\_\_\_\_  
 T \_\_\_\_\_ R \_\_\_\_\_

2. Property Controlling S \_\_\_\_\_ T \_\_\_\_\_  
 in Section S \_\_\_\_\_ T \_\_\_\_\_

3. Miscellaneous S \_\_\_\_\_ T \_\_\_\_\_  
 Property in Sec. S \_\_\_\_\_ T \_\_\_\_\_

4. Lot No. \_\_\_\_\_ Recorded Plat \_\_\_\_\_

5. Private Claims \_\_\_\_\_

REGISTER'S OFFICE  
MANISTEE COUNTY

#96-368 at 10:35 A.M.

AUG 23 1996

*Penny A. Repora*  
REGISTER OF DEEDS

Register of Deeds Stamp & File Number

I, Kenneth L. Ross, in a field survey on July 17, 1996, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

- M-9 Sec. Cor., 24 & 25-21-13  
 1839 John Brink  
 (1) 10" P. Pine S 55 W 12 lks  
 (2) 9" P. Pine N 67.5 W 13 lks

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

- M-9 Sec. Cor., 24 & 25-21-13 *set*  
 July, 1909, Fargo Eng. Co. #1 1" Iron Pipe with lime around (Book A, Page 8)  
 (3) 9" R. Oak N 02 W 194 lks  
 (4) 10" R. Oak S 76.5 E 234 lks  
 Oct., 1963, Robert Griffin Fd. line & rust marks but no 1" Iron Pipe, also Fd. stumps of 3 & 4, set 5" x 3' Square Reinforced Concrete Post set 1' below road surface and filed Act 74 (June 1973) Liber 73, Page 70  
 (5) 10" dock spike in 7" B. Oak (scribed ST) N 57 E 89.25'  
 (6) 6" x 7' Cedar Post East 33'  
 (7) 10" dock spike in 4" W. Oak S 49 E 77.00'  
 (8) 10" dock spike in 5" W. Oak S 83 W 50.45'  
 (9) 10" dock spike in 4" B. Oak N 23 W 93.10'  
 Aug., 1992, Norman Caldwell for USDA Forest Service Fd. 5" Square Concrete Post per Liber 73, Page 70  
 same witness as #5, 6, 7, 8, & 9  
 July, 1996, K. Ross Fd. 5" x 3' Square Reinforced Concrete Post as set by Griffin, in West Wheel Track of N-S 2-tr. Road

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- M-9 Sec. Cor., 24 & 25-21-13  
 Fd. Witness #7 (now 6.5"), 8 (now 12"), & 9 (now 6.5", spike in root 11.5" under ground).  
 Witness #1, 2, 3, 4, 5, & 6 gone.  
 Left 5" x 3' Square Reinforced Concrete Post in place, and is accepted as the best available evidence of the original corner.  
 (10) 12" B. Oak N 53 E 110.21' (Spike)

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

Corner M-29 ratified by the Manistee County Peer Group according to the county plan adopted pursuant to P.A. 345 of 1990, as amended, (being the State Survey and Reentryment Act, MCL 54.261 et seq.). Date of Peer Review: AUG 1996

*Anthony M. Slawinski*

Signed by *[Signature]* Date 8-5-96

Surveyor's Michigan License No. 17634

