

MEMORANDUM

MAY 18 1997

COMMISSION

LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. P.A. 1970

Form for recording corners with fields for County (Manistee), Located In, Corner Code #, and numbered items 1-5.

REGISTER'S OFFICE MANISTEE COUNTY

#96-369 AT 10:38 A.M. AUG 23 1996

Signature of Penny A. Pepera, REGISTER OF DEEDS

Register of Deeds Stamp & File Number

I, Kenneth L. Ross, in a field survey on July 17, 1996, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, re-monumented, recovered, found as expressed below.

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

- M-10 1/4 Cor., 25-21-13 1839 John Brink (1) 12" P. Pine S 67 W 17 lks (2) 10" P. Pine N 37 W 17 lks

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

- M-10 1/4 Cor., 25-21-13 July, 1909, Fargo Eng. Co. set 1" Iron Pipe with lime around (Book A, Page 14) (3) 6" R. Oak S 73 W 93.5 lks (4) 8" R. Oak S 27.25 E 92 lks Jun., 1926, J. H. Millard Set Iron (Book A, Page 14) (5) B. Oak N 02 W 194 lks (6) 10" B. Oak S 76 E 234 lks Aug., 1963, Robert Griffin Fd. 1 1/4" Well Point with lime around and 3 & 4, replaced with 5" x 3" Square Reinforced Concrete Post set 1.5' below road surface and filed Act 74 (June 1973) Liber 73, Page 69 (7) 3/4" Iron Pipe (P.I. gravel roads S&E) N 01 E 146.00' (8) 10" dock spike in 8" B. Oak (scribed BT) S 40 E 114' (9) 10" dock spike in 8" W. Oak (scribed BT) N 18 W 83.85' (10) Center 20" B. Oak S 27.25 E 61.50' (11) "X" on cusp of boulder S 17 W 126.10' (12) Center 19" B. Oak S 73 W 61.55' (13) 5" x 7' Cedar Post West 33' (14) 10" dock spike in 4" W. Oak (scribed BT) N 82 W 88.10' Sep., 1982, Ray Fd. USFS Monument (Liber 3, Page 336 Wexford County) (15) Power Pole S 56 E 140.76' (16) Nail in 10" Oak N 14 E 50.43' (17) Nail in Wit. Post West 33.10' Aug., 1992, Norman Caldwell for USDA Forest Service Fd. 5" Square Concrete Post per Liber 73, Page 69 same witness as # 7, 8, 9, 10, 11, 12, 13, & 14 July, 1996, K. Ross Fd. 5" x 3" Square Reinforced Concrete Post as set by Griffin, 2.5' below road surface, 6.5' West of West Edge Asphalt, W/1/2" Iron Riser 0.15' from center

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner.

- M-10 1/4 Cor., 25-21-13 Fd. Witness #9 (now 15") & 16 (now 15"). Witness #13 & 17 appear to be the same, Fd. Nail W/Shiner in Post West 33.31'; four blazed trees were also found as shown in #18, 19, 20, & 21. Witness #1, 2, 3, 4, 5, 6, 7, 8, 10, 11, 12, 14, & 15 gone. Left 5" x 3" Square Reinforced Concrete Post in place, Reset 1/2" Iron Riser in correct position W/Yellow Cap #17634, and is accepted as the best available evidence of the original corner. (18) 15" W. Oak (tag printed 1963) N 18 W 83.62' (Spike) (19) 24" B. Oak (tag printed 5-89 SJS) S 53 E 83.36' (Spike) (20) 10" W. Oak (tag printed N 77 W 88.02) N 77 W 88.13' (Spike) (21) 25" W. Oak (tag printed S 58 E 83.36) S 62 E 83.34' (Spike) (22) Highest Point on 3' x 3' x 2' Boulder S 21 W 133.21' (23) 1/2" Iron at approximate PI Roads South & East North 143.46'

Grid table with columns A-M and rows 1-13, containing numbers 1-36.

Corner M-10 ratified by the Manistee County Peer Group according to the county plan adopted pursuant to P.A. 345 of 1990, as amended, (being the State Survey and Remonument Act, MCL 54.261 et seq.). Date of Peer Review: AUG 6 1996

Signature of Anthony M. Slawinski

Signed by [Signature] 8-5-96 Date

Surveyor's Michigan License No. 17634

