

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

Manistee Located In: Corner Code #
 (County)

1. Public Land Survey T 21N R 15 W M-5
 T 21N R 14 W A-05 ✓
 T R
 T R
 2. Property Controlling S T R
 in Section S T R
 3. Miscellaneous S T R
 Property in Sec. S T R

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

I, Bruce J. Jenema, in a field survey on April 27, 19 98 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

M-5 1837, J. Brink, G.L.O. Set post (1) W. Pine 11° S74°W 16 lk. (10.56') (2) Y. Pine 20° N65 ½°W 64 lk. (42.24')	1986, K. Ross Fd. USFS Monument (6) W. Oak 7° S57°W 6.62' (7) Corn. of Cabin S40°W 75.55' (8) W. Oak 14° S63°E 51.87' (9) Pine Stump N11°E 36.35'
1907, J.H.M. (3) W. Pine Stump 12° N28°E 35 lk. (23.1')	1993, J. Ray Fd. USFS Monument (4) (6) (9) (10) USFS Post North 1.3' (11) Oak 28° N25°W 34.06'
1974, A.M. Slawinski Fd. iron pipe (4) W. Oak 18° SE 51.87' (5) W. Pine 5° NE 57.46'	

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

On April 27, 1998 I found a 5" x 36" concrete monument with a brass cap 6 in. above the ground surface.
 No conflicting evidence of other corners existing.
 Condition of record accessories to corners:
 (1) & (2) - extinct
 Fd. (7) (8) (9) (10) in good condition

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

NE corner, section 13, accepted USFS concrete monument as a substantial monument and is accepted as a careful and faithful reestablishment of the position of the original corner and is witnessed by the found accessories:

- (7) Corn. of Cabin S40°W 75.55 ft.
- (8) W. Oak 14° S63°E 51.87 ft. face of tree
- (9) Pine stump N11°E 36.35 ft. Old face SE side
- (10) USFS Post North 1.3 ft. spike W. side
- (11) Oak 28° N25°W 34.06 ft. spike W. side
- (12) W. Pine 10° N75°E 54.37' 50-D W. side

Corner M - O S ratified by the Manistee County Peer Group according to the county plan adopted pursuant to P.A. 345 of 1990, as amended, (being the State Survey and Remonument Act, MCL 54.261 et seq.). Date of Peer Review: Anthony M. Slawinski

AUG 04 1998

Signed by Bruce J. Jenema
 Surveyor's Michigan License No. 25850

Date 8-11-98

REGISTER'S OFFICE
MANISTEE COUNTY
 98-381 at 11:10am
SEP 17 1998
Deborah Dix
REGISTER OF DEEDS

Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6			5			4			3			2
3													
4	7			8			9			10			11
5													
6	18			17			16			15			14
7													
8	19			20			21			22			23
9													
10	30			29			28			27			26
11													
12	31			32			33			34			35
13													

REGISTERED
 FEB 11 2000
 SECTION

