

DEC 28 1998

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

SECTION

For corners in

<u>Manistee</u>	Located In:	Corner Code #
(County)		
1. Public Land Survey	T 21 st R 15 th	M-7
	T 21 st R 14 th	AOT ✓
	T R	
	T R	
2. Property Controlling in Section	S T R	
	S T R	
3. Miscellaneous Property in Sec.	S T R	
	S T R	

REGISTER'S OFFICE
MANISTEE COUNTY
98-378 at 10:55am
SEP 17 1998
B. Jenema
REGISTER OF DEEDS

Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, Bruce J. Jenema, in a field survey on April 27, 19 98 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

- | | |
|---|---------------------------------|
| M-7 1837, J. Brink, G.L.O. | 1986, K. Ross |
| Set post common to section 13 & 24 | 1/2" x 24" iron with cap #17643 |
| (1) W. Pine 30° S26°W 31 lk. (20.46') | (4) W. Oak 12° N33°E 34.66' |
| (2) W. Pine 28° N50°W 20 lk. (13.2') | (5) Maple 10° S32°E 23.52' |
| | (6) Oak 8° S40°W 29.19' |
| 1907, J.H.M. | (7) Carsonite post North 1.0' |
| Fd. corner and bearing trees | |
| (3) W. Pine Stump 24° N27°W 15 lk. (9.9') | |
| 1908, D. Skeels, "old corner" | |

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

On April 27, 1998 I found a 1/2" x 24" iron with cap #17643. No conflicting evidence of other corners existing
(1) (2) - now extinct
(3) W. Pine Stump 24° N27°W 10.0'
(4) (5) (6) (7)

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

On May 5, 1998 I placed a standard Manistee County Monument in the exact position of the above 1/2" x 24" iron bar and is accepted as the best available evidence of the position of the original corner and witnessed by:

- (4) W. Oak 12° N33°E 34.66' spike S. side
- (5) Maple 10° S32°E 23.52' spike W. side
- (6) Oak 8° S40°W 29.19' spike N. side
- (7) Carsonite post North 1.0'
- (8) Oak 8° N90°W 12.90'

Corner M-07 ratified by the Manistee County Peer Group according to the county plan adopted pursuant to P.A. 345 of 1990, as amended, (being the State Survey and Remonument Act MCL 54.261 et seq.). Date of Peer Review: Anthony M. Slawinski

AUG 04 1998

Signed by Bruce J. Jenema
Surveyor's Michigan License No. 25850

Date 08-04-98

