

LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

FOR CORNERS OF--	LOCATED IN--	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY	T. 21N N. 14W E. S., R. W.	D7
2. PROPERTY CONTROLLING IN SECTION	T. N. S., R. E. W.	
3. MISCELLANEOUS PROPERTY IN SECTION	T. N. S., R. E. W.	
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER'S OFFICE
MANISTEE COUNTY
 #93-206 AT 10:48
APR 20 1993
Penny A. Perna
REGISTER OF DEEDS

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, Patrick R. Leemon do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970 the corner points mentioned in lines 1 and 2 above (identified with circles on index code diagram—over) were, in field survey on January 23 1993 established, re-established, monumented, re-monumented, recovered restored as expressed below and in conformance with regulations and rules therefore as required in the current manu of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey of _____ 19____, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court law:

A. Description of original monument and accessories and/or subsequent restoration:

1/4 corner common to sections 17 and 20 of T21N R14W
 1979 Survey by Robert A. Griffin
 Monu. Set 5" sq. by 60" long concrete monu. with 3" brass disk.
 Witnesses
 W.Pine 8 N56E 98.00'
 P.Pole S66E 23.87'
 W.Pine 7 S25E 83.24'
 Pine Post 3 North 2.11'

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

I found the monument and all the witnesses to be in good condition. The monument extends 1.5' above the surface. Liber 80 Page 21 documents the history of this corner as perpetuated by Griffin. No evidence was found of the original or any subsequent surveys and the position was recovered using proper techniques. I accept this position as an accurate representation of the original location.

C. Description of monument for corner and accessories established to perpetuate locating the position of corner:

1/4 corner common to sections 17 and 20 of T21N R14W
 Monu. 5" sq. by 60" long concrete monu. with 3" brass disk.
 Witnesses
 W.Pine 8 N56E 98.00'
 P.Pole S66E 23.87'
 W.Pine 7 S25E 83.24'
 Pine Post 3 North 2.11'
 Iron Fence Post S40W 1.8'
 Centerline of E-W road is North 90'

Corner D-2 ratified by the Manistee County Peer Group pursuant to P.A. 123 of 1915 as amended by P.A. 345 of 1990 as amended. Date of Peer Review: FEB. 11 1993

SURVEY & REMONUMENTATION

1993

COMMISSION

SIGNED BY *Patrick R. Leemon* DATE January 25, 1993

SURVEYOR'S MICHIGAN REGISTRATION NO. 31595

FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY _____ DATE _____
CHIEF OF SURVEY PARTY

APPROVED AND SIGNED BY _____ DATE _____
MICHIGAN REGISTERED LAND SURVEYOR

SURVEYOR'S MICHIGAN REGISTRATION NO. _____

