

LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

FOR CORNERS OF—	LOCATED IN—	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY _____ T. _____	21N N. 14W E. S., R. W.	1-7
2. PROPERTY CONTROLLING IN SECTION _____ T. _____	N. E. S., R. W.	_____
3. MISCELLANEOUS PROPERTY IN SECTION _____ T. _____	N. E. S., R. W.	_____
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER'S OFFICE
MANISTEE COUNTY
#93-210 AT 11:20 A.M.
APR 20 1993
Tommy A. Pomeroy
REGISTER OF DEEDS

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, Patrick R. Leemon do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above (identified with circles on index code diagram—over) were, in a field survey on January 23 1993, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on _____ 19____, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. Description of original monument and accessories and/or subsequent restoration:

Section corner common to sections 14, 15, 22 and 23 of T21N R14W
 1963 Survey by Robert A. Griffin
 Monu. Set 6" round by 60" long concrete monu. with 3" brass disk.
 Witnesses
 Cedar 6 N36E 26.10'
 Tw.W.Oak 17 S74W 45.15'
 Cedar 7 N25W 40.15'
 Iron Pipe 1"x36" S22W 15.23'

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

I found the monument and all the witnesses except the Iron Pipe which I did not look for. The 7" Cedar N25W has been cut. The monument extends 1.2' above the surface. Liber 73 Page 57 documents the history of this corner as perpetuated by Griffin.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Section corner common to sections 14, 15, 22 and 23 of T21N R14W
 Monu. 6" round by 60" long concrete monu. with 3" brass disk.
 Witnesses
 Cedar 6 N36E 26.10'
 Tw.W.Oak 17 S74W 45.15'
 B.Oak 18 N80W 8.38'
 W.Cedar 6 N32W 32.00'
 Fiberglass Post North 1.2'
 Corner is on centerline of road to south and 14' north of centerline of road to east.
 Centerline of N-S Powerline is West 27'

Corner i - z ratified by the Manistee County Peer Group pursuant to P.A. 123 of 1976, as amended by P.A. 345 of 1990, as amended. Date of Peer Review: FEB 1 1993

SURVEY & REMONUMENTATION

1993

COMMISSION

SIGNED BY *Patrick R. Leemon* DATE January 25, 1993

SURVEYOR'S MICHIGAN REGISTRATION NO. 31595

FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY _____ DATE _____
CHIEF OF SURVEY PARTY

APPROVED AND SIGNED BY _____ DATE _____
MICHIGAN REGISTERED LAND SURVEYOR



SURVEYOR'S MICHIGAN REGISTRATION NO. _____