

LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

FOR CORNERS OF--:	LOCATED IN--:	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY _____	T. <u>21N</u> N. <u>14W</u> E. S., R. _____ W.	1-8
2. PROPERTY CONTROLLING IN SECTION _____	T. _____ N. _____ E. S., R. _____ W.	_____
3. MISCELLANEOUS PROPERTY IN SECTION _____	T. _____ N. _____ E. S., R. _____ W.	_____
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER'S OFFICE
MANISTEE COUNTY
#93-209 AT 11:15 A.M
APR 20 1993
Penny A. Parnas
REGISTER OF DEEDS

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, Patrick R. Leemon do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above (identified with circles on index code diagram - over) were, in a field survey on January 23 1993, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on _____ 19____, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. Description of original monument and accessories and/or subsequent restoration:

1/4 corner common to sections 22 and 23 of T21N R14W
 1977 Survey by Robert A. Griffin
 Monu. Set 5" sq. by 60" long concrete monu. with 3" brass disk.
 Witnesses
 R.Oak 4 S11E 29.44'
 R.Maple 5 S33W 14.17'
 R.Maple 7 N52W 6.13'
 Pine Post 4 North 1.25'

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

I found the monument and all the witnesses to be in good condition. The monument extends 1.2' above the surface. Liber 79 Page 12 documents the history of this corner as perpetuated by Griffin. I could find no evidence of the 1836 GLO post or witnesses.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

1/4 corner common to sections 22 and 23 of T21N R14W
 Monu. 5" sq. by 60" long concrete monu. with 3" brass disk.
 Witnesses
 R.Oak 8 S11E 29.44'
 R.Maple 6 S33W 14.17'
 R.Maple 10 N52W 6.13'
 Pine Post 4 North 1.25'
 R.Maple 6 N55E 29.27'
 Corner is off centerline of the road to the north and 75' south of centerline of road to the west.

ratified by the Manistee
 Peer Group pursuant to P.A. 123 of
 as amended by P.A. 345 of 1990, as
 Date of Peer Review: **FEB 1 1993**

SURVEY & RE-MONUMENTATION

1993

COMMISSION


SIGNED BY *Patrick R. Leemon* DATE January 25, 1993

SURVEYOR'S, MICHIGAN REGISTRATION NO. 31595

FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY _____ DATE _____
CHIEF OF SURVEY PARTY

APPROVED AND SIGNED BY _____ DATE _____
MICHIGAN REGISTERED LAND SURVEYOR



SURVEYOR'S MICHIGAN REGISTRATION NO. _____