

# LAND CORNER RECORDATION CERTIFICATE

## FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

FOR CORNERS OF--	LOCATED IN--	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY _____, T. _____, R. _____	21N N. 14W E. S., R. _____ W.	I-10
2. PROPERTY CONTROLLING IN SECTION _____, T. _____, R. _____	N. _____ E. S., R. _____ W.	_____
3. MISCELLANEOUS PROPERTY IN SECTION _____, T. _____, R. _____	N. _____ E. S., R. _____ W.	_____
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER'S OFFICE  
MANISTEE COUNTY  
#93-211 AT 11:27 A.M.  
**APR 20 1993**  
*Penney A. Leemon*  
REGISTER OF DEEDS

---

REGISTER OF DEEDS STAMP AND  
FILING NUMBER

I, Patrick R. Leemon do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above (identified with circles on index code diagram—over) were, in a field survey on January 23 1993, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on \_\_\_\_\_ 19\_\_\_\_, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

**A. Description of original monument and accessories and/or subsequent restoration:**

**1/4 corner common to sections 26 and 27 T21N R14W**  
1978 Survey by Robert A. Griffin  
Monu. Set 5" sq. by 60" long concrete monu. with 3" brass disk.  
Witnesses  
R. Maple 7 S56W 8.62'  
Basswood 19 N13E 13.14'  
Pine Post East 2.28'  
Basswood 8 S45E 27.09'

**B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:**

I found the monument and all but one of the witnesses to be in good condition. The monument extends 1.4' above the surface. Liber 79 Page 9 documents the history of this corner as perpetuated by Griffin. I could find no evidence of the 1838 GLO post or witnesses.

**C. Description of monument for corner and accessories established to perpetuate locating the position of corner:**

**1/4 corner common to sections 26 and 27 T21N R14W**  
Monu. 5" sq. by 60" long concrete monu. with 3" brass disk.  
Witnesses  
R. Maple 7 S56W 8.62'  
Basswood 19 N13E 13.14'  
Pine Post 4 East 2.28'  
Basswood 10 S45E 27.09' (top is broken off)  
B. Ash 3 N76E 39.45  
Centerline of SW-NE 2-track is south 140'

Corner i - 10 ratified by the Manistee County Peer Group pursuant to P.A. 123 of 1915, as amended by P.A. 116 of 1989, as amended. Date of Peer Review: FEB of 1993.

SURVEYOR  
**REMONUMENTATION**  
= 1993  
**COMMISSION**

SIGNED BY *Patrick R. Leemon* DATE January 23, 1993  
SURVEYOR'S MICHIGAN REGISTRATION NO. 31595  
FOR STATE AND UNITED STATES AGENCIES:  
SIGNED BY \_\_\_\_\_ DATE \_\_\_\_\_  
CHIEF OF SURVEY PARTY  
APPROVED AND SIGNED BY \_\_\_\_\_ DATE \_\_\_\_\_  
MICHIGAN REGISTERED LAND SURVEYOR

