

DEC 28 1998

LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. P.A. 1970

SECTION

REGISTER'S OFFICE
MANISTEE COUNTY
98-275 at 3:25pm
JUL 07 1998
Deborah Six
REGISTER OF DEEDS

For corners in MANISTEE (County) Located in: Corner Code #
1. Public Land Survey T 21N R 14W L-13
2. Property Controlling In section S T R
3. Miscellaneous Property in Sec. S T R

Register of Deeds Stamp & File Number

4. Lot No. Recorded Plat
5. Private Claims

I, Kenneth L. Ross, in a field survey on June 3, 1998, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

Grid table with columns A-L and rows 1-13. Numbers 1-36 are placed in the grid cells.

A. Description of original monument and accessories and/or subsequent restoration:

L-13 South 1/4 corner for Section 36, on the Township-Line, T21N-R14W.

1838, John Brink, G.L.O. boundary survey Set Wood Post at 40 chs.
#1 Black Oak 8" N 23 W 34 lks. (15.18')
#2 White Oak 16" N 17 E 50 lks. (33.00')

1907, John H. Millard, M.C.S. Millard established this corner by single pro-rate Monument not-given (book "A" Page 32).
#3 White Pine Stump 24" N 18 E 56 lks. (36.96')
#4 White Pine stump 24" N 29 W 40 lks. (26.40')

1988, Kenneth L. Ross, RLS#17634 Set 1/2" Re-Rod at single proportional method. 2645.29' to the controlling corners. (file no. 32288a.)
#5 Maple 8' N 45 E 33.53'
#6 Red Oak 14" N 30 W 38.44'
#7 Power-Pole 8 32 E 59.08'
#8 White Oak 8" S 26 W 68.31'
1993, Anthony M. Slawinski, RLS#13597 Used Ross 1/2" Re-Rod in Property Survey, Liber 2, page 522

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

L-13 South 1/4 corner for Section 36, on the Township-Line, T21N-R14W.

On June 3, 1998, I found 1/2" Re-Rod set by me ten years previous in property survey. I search area for record evidence but found none.

Condition of record witnesses as follows are: #1 gone #2 gone #3 gone #4 gone #5 found in good condition #6 found in good condition #7 found in good condition #8 found in good condition

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

L-13 South 1/4 corner for Section 36, on the Township-Line, T21N-R14W.

I replaced 1/2" Re-Rod in the exact location with a standard Manistee County Monument stamped to identify this corner, set monument 1.0' below the surface of road. This corner is accepted as a careful and faithful re-establishment of the position of the original corner.

Ext. "BT" #5 Maple 10" N 45 E 33.53' (60d spike in SE side of tree)
Ext. "BT" #6 Red Oak 14" N 30 W 38.44' (60d spike in SW side of tree)
Ext. "BT" #7 Power-Pole 8 32 E 59.08' (60d spike in SW side of pole)
Ext. "BT" #8 White Oak 10" S 26 W 68.31' (60d spike in NW side of tree)

ratified by the Manistee County Peer Group according to the county plan adopted pursuant to P.A. 345 of 1990, as amended, (being the State Survey and Re-surveyment Act, MCL 54.261 et. seq.) - Date of Peer Review: JUL 7 1998

Anthony M. Slawinski

Signed by [Signature] Date July 2, 1998
Surveyor's Michigan License No. 17634

