

**LAND CORNER RECORDATION CERTIFICATE**  
**Filing Requirement of Act 74, Mich. P.A. 1970**

For corners in MANISTEE Located In: \_\_\_\_\_ Corner Code # \_\_\_\_\_  
 (County)

1. Public Land Survey T 21N R 17W G-13  
 T \_\_\_\_\_ R \_\_\_\_\_  
 T \_\_\_\_\_ R \_\_\_\_\_  
 T \_\_\_\_\_ R \_\_\_\_\_

2. Property Controlling S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_  
 in Section S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_

3. Miscellaneous S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_  
 Property in Sec. S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_

**REGISTER'S OFFICE**  
**MANISTEE COUNTY**  
 98-255 at 4:00pm  
**JUL 0 1 1998**  
*Richard Dix*  
**REGISTER OF DEEDS**

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_ Recorded Plat \_\_\_\_\_  
 5. Private Claims \_\_\_\_\_

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, Richard L. Hays, in a field survey on April 1998, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

**A. Description of original monument and accessories and/or subsequent restoration:**

**SOUTHEAST QUARTER CORNER OF SECTION 33, T21N-R17W**  
 1838: G.L.O. Survey by John Brink Set post. 1979: Nordlund, Dunlap Survey  
 10" Beech N-74°-E 46 Lks (1) Fence Post N-45°-W 66.10' (7)  
 18" Hemlock N-35°-W 22 Lks (2) Fence Post N-45°-E 48.15' (8)  
 Street Sign South 18.47' (9)

1900: J.H.M Survey (HWY. Comm.) Book A, Page 82. Set Stake & Stones 1993: Anthony Slawinski Survey  
 36" White Pine Stump S-29°-E 26 Lks (3) Found 1" Iron Pipe  
 No Witnesses

1969: T.J. Vallien Court  
 1-1/4" Iron Pipe  
 Fence post Northwest 45.95' (4)  
 Power Pole Southeast 95.00' (5)  
 Third Fence Post from Corner  
 Northeast 98.15' (6)

**B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:**

**SOUTHEAST QUARTER CORNER OF SECTION 33, T21N-R17W**  
 APRIL 1998: Found 5/8" Rod in Monument Box in the intersection of East-West and North Road. Condition of the witnesses are as follows:

10" Beech	N-74°-E	46 Lks (1) GONE
18" Hemlock	N-35°-W	22 Lks (2) GONE
36" White Pine Stump	S-29°-E	26 Lks (3) GONE
Fence post	Northwest	45.95' (4) GONE
Power Pole	Southeast	95.00' (5) FOUND
Third Fence Post from Corner	Northeast	98.15' (6) GONE
Fence Post	N-45°-W	66.10' (7) GONE
Fence Post	N-45°-E	48.15' (8) GONE
Street Sign	South	18.47' (9) GONE

**C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:**

**SOUTHEAST QUARTER CORNER OF SECTION 33, T21N-R17W**  
 APRIL 1998: Accepted 5/8" Rod in Monument Box and replaced with Manistee County Monument as the best available evidence of the position of the Corner.  
 1993 MAGO Bench Mark-Aluminum Monument in Concrete N-43°-W 89.80'  
 MDOT Nail in Power Pole N-36°-E 94.97' (5)  
 Set 1/2" Re-Rod N-76°-E 57.50'  
 Set 1/2" Re-Rod S-41°-W 19.10'

Corner G-13 ratified by the Manistee County Peer Group according to the county plan adopted pursuant to P.A. 345 of 1998 as amended, (being the State Survey and Re-monument Act, MCL 54.2 et seq.). Date of Peer Review MAY 5 1998

*Anthony M. Slawinski*

Signed by Richard Hays Date May 1, 1998

Surveyor's Michigan License No. 25847

