

**LAND CORNER RECORDATION CERTIFICATE**

**Filing Requirement of Act 74, Mich. P.A. 1970**

SECTION

For corners in  
MANISTEE  
 (County)

Located In: Corner Code #

1. Public Land Survey T 21N R 17W I-13  
 T R  
 T R  
 T R

2. Property Controlling S T R  
 in Section S T R

3. Miscellaneous S T R  
 Property in Sec. S T R

**REGISTER'S OFFICE  
 MANISTEE COUNTY**

98-363 at 4:15pm  
**JUL 01 1998**

*Reborah Six*  
**REGISTER OF DEEDS**

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
 5. Private Claims \_\_\_\_\_

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, Richard L. Hays, in a field survey on April 1998, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

**A. Description of original monument and accessories and/or subsequent restoration:**

SOUTHEAST CORNER OF SECTION 34, T21N-R17W  
 1838: G.L.O. Survey by John Brink Set Post 1985: Slawinski Survey Act 132-Liber 1, page 830  
 10" Maple N-34°-W 25 Lks(1) 1" Iron Pipe - NO WITNESSES  
 10" Hemlock N-19°-W 15 Lks(2)

1962: Anthony Slawinski Survey, Act 132-Liber 1, page 191  
 1" Iron Pipe NO WITNESSES

1974: Survey by Herbert Fluharty Act 74 #74-32  
 Found 3/4" Iron Pipe  
 Act 132, Liber 1, Page 191  
 10" Oak N-39°-E 63.70' (3)  
 7" Pine N-45°-E 64.91' (4)  
 6" Poplar S-10°-W 29.13' (5)

**B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:**

SOUTHEAST CORNER OF SECTION 34, T21N-R17W  
 APRIL 1998: Found 1-1/4" Pipe in Monument Box, 3.1' North of the Centerline of County Line Road and on the Centerline of Wild Wood Road to the North, Condition of the witnesses are as follows:  
 10" Maple N-34°-W 25 Lks(1) GONE  
 10" Hemlock N-19°-W 15 Lks(2) GONE  
 10" Oak N-39°-E 63.70' (3) FOUND  
 7" Pine N-45°-E 64.91' (4) FOUND  
 6" Poplar S-10°-W 29.13' (5) GONE

**C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:**

SOUTHEAST CORNER OF SECTION 34, T21N-R17W  
 APRIL 1998: Accepted 1-1/4" Iron Pipe in Monument box and replaced with a MANISTEE COUNTY MONUMENT as the best available evidence of the position of the Corner.  
 7" Maple Clump S-35°-W 42.33' 60 Penny Nail  
 7" Jackpine S-22°-E 36.08' 60 Penny Nail  
 Tagged 16" Black Oak N-45°-E 63.70' (3)  
 RR Tie Fence Corner N-44°-W 44.48' 60 Penny Nail

Corner I-13 ratified by the Manistee County Peer Group according to the county plan adopted pursuant to P.A. 345 of 1980, as amended, (being the State Survey and Remonument Act, MCL 54.261 et. seq.). Date of Peer Review: MAY 5 1998

*Anthony M. Slawinski*

Signed by Richard Hays  
 Surveyor's Michigan License No. 25847

