

PERSONAL PROPERTY

DEC 2 9 1996

COUNTY

LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

<u>Manistee</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T 21N R 17W	K-04
	T _____ R _____	East 1/4 Corner
	T _____ R _____	Section 11
	T _____ R _____	
2. Property Controlling in Section	S _____ T _____ R _____	
	S _____ T _____ R _____	
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	
	S _____ T _____ R _____	

REGISTER'S OFFICE
MANISTEE COUNTY

97-392 at 3:40pm
OCT 17 1997

Reborah Six

REGISTER OF DEEDS

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, Anthony M. Slawinski, in a field survey on July 29, 19 97 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:
K-04 East 1/4 Corner of Section 11, T21N., R17W.

Set by John Brink in 1837

Set West Section Post, Section 12 (T21N., R17W.)

- 1. Beech 12" N 38° E 31 links (Gone)
- 2. Hemlock 18" S 58° W 30 links (Gone)

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
K-04 East 1/4 Corner of Section 11, T21N., R17W.

Found 3/4" Iron Pipe by Slawinski (1955)

- 3. NE 42.78' Power Pole (Gone)
- 4. SE 42.73' Power Pole (Gone)
- 5. SW 32.13' Power Pole
- 6. NW 40.69' Power Pole

Also referenced:

GLO Field Notes by John Brink (1837) Book 1, Page 429

Slawinski Field Notes (1984)

Engelwood Plat (5-23-1881), Vol. 2 of Plats, Page 40

Mark S. Tyson & Co.'s Addition(9-2-1867),
Liber 5, Pages 218 & 219

On July 29, 1997 a 3/4" Iron Pipe was found by Anthony Slawinski & Abonmarche. Below the pipe a chiseled "X" in concrete was found.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
K-04 East 1/4 Corner of Section 11, T21N., R17W.


On July 29, 1997, I installed a Manistee County Monument, within a monument box, in the exact location of the above 3/4" Iron Pipe and chiseled "X" as a careful and faithful re-establishment of the position of the original corner, and witnessed by:

- 5. S 55° W 32.03' Power Pole (Spike in the Northeast side)
- 6. N 56° W 40.75' Power Pole (Spike in the Northeast Side)
- 7. N 70° E 52.00' 24" Maple (Spike in the Southeast side)
- 8. S 54° E 47.23' 14" Maple (Spike in the Northeast side)

This corner was set at the intersection of the center lines of 5th Street and Maple Street

Signed by Anthony M. Slawinski
Surveyor's Michigan License No. 13597

Date 10-2-97



Corner K-04 ratified by the Manistee County Peer Group according to the county plan adopted pursuant to P.A. 345 of 1990, as amended, (being the State Survey and Remonument Act, MCL 54.261 et. seq.). Date of Peer Review: OCT 7 1997

FORM APPROVED BY MICHIGAN STATE BOARD OF