

129

SECTION LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

Manistee (County) Located In: Corner Code #
1. Public Land Survey T 21N R 17W L-05
South 1/4 Cor.
Sec. 12
2. Property Controlling S T R
in Section S T R
3. Miscellaneous S T R
Property in Sec. S T R
4. Lot No. , Recorded Plat
5. Private Claims

REGISTER'S OFFICE MANISTEE COUNTY

98-242 at 9:15am JUN 29 1998

REGISTER OF DEEDS

Register of Deeds Stamp & File Number

I, Anthony M. Slawinski, in a field survey on May 19, 1998 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and for that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

Set by John Brink in 1839

- 1. Hemlock 16" West 16 links (Gone)
2. White Pine 12" N 30° E 22 links (Gone)

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Michigan Department of Transportation Notes & Map (1946-47)

Survey Certificate by Slawinski (1970)

Field Notes by Slawinski (1970)

- 3. N 20° W 62.48' Power Pole (Good)
4. N 20° E 98.62' 24" Maple, tag ±9" high (Gone)
5. N 75° E 93.58' Telephone Pole, tag ±8" high (Gone)
6. S 45° E 54.41' N.W. Corner of house (foundation) (Good)

L.C.R.C. by Butterfield (1980)

- Found 1" iron pipe
4. N 20° E 98.54' 24" Maple (nail & tag in S.W. face) (Gone)
3. N 20° W 62.56' Utility Pole (nail & tag in N.E. face) (Good)
7. S 45° W 32.11' Utility Pole (nail & tag in S.E. face) (Good)
8. S 45° W 53.93' N.W. Corner of house

Lake Winnogene Suburb to the City of Manistee (6-14-1881) Volume 2 of Plats, Page 21

Survey Certificate by Butterfield (1980)

Survey Certificate by Slawinski (1996)

On May 19, 1998, I Anthony Slawinski, along with Abonmarche found a 1" Iron pipe.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

On May 19, 1998, I installed a Manistee County Monument, in the exact location as the above mentioned 1" iron pipe, as a careful and faithful re-establishment of the position of the original corner and witnessed by:

- 3. N 17° W 62.56' Power Pole, 16D nail & tag in West side
6. S 36° E 54.41' Northwest Corner of house foundation
7. S 36° W 31.09' Power Pole, 16D nail & tag in Southeast side
9. N 27° E 47.83' Top center of Fire Hydrant

Note: Corner is 1.25' South of South side of Twelfth Street asphalt on center line of Davis Street extended, approximately 222' east of the centerline of highway U.S. - 31.

Grid table with columns A-M and rows 1-13. A dot is present in cell J5.

ratified by the Manistee County Peer Group according to the county plan adopted pursuant to P.A. 345 of 1996 as amended, (being the State Survey and Monument Act, MCL 54.263 et seq.). Date of Peer Review: Anthony M. Slawinski

JUN 29 1998



Signed by Anthony M. Slawinski

Surveyor's Michigan License No. 13597

Date 6-1-98