


**SURVEY & REMONUMENTATION**

**APR 07 1998**

**LAND CORNER RECORDATION CERTIFICATE**  
 Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

<u>Manistee</u> SECTION (County)	Located In:	Corner Code #/
1. Public Land Survey	T <u>21N.</u> , R <u>17W.</u>	<u>M-6 WC</u>
	T _____ R _____	<u>W of E 1/4 Sec.</u>
	T _____ R _____	<u>13</u>
	T _____ R _____	
2. Property Controlling in Section	S _____ T _____ R _____	
	S _____ T _____ R _____	
3. Miscellaneous	S _____ T _____ R _____	
	S _____ T _____ R _____	
Property in Sec.	S _____ T _____ R _____	

**REGISTER'S OFFICE  
 MANISTEE COUNTY**

97-394 at 3:50pm  
**OCT 17 1997**

*Kebonah*

**REGISTER OF DEEDS**

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
 5. Private Claims \_\_\_\_\_

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	13		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

I, Anthony M. Slawinski field survey on July 28, 1997, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

**A. Description of original monument and accessories and/or subsequent restoration:**

M-6 East 1/4 Corner of Section 13, T21N., R17W

Corner not set, in Manistee Lake  
 by John Brink, 1848

**B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:**

M-6 WC West of the East 1/4 Corner of Section 13, T21N., R17W.

Established the East 1/4 Corner of section 13 by intersecting the North-South Range line and the Indian Reservation Line, which is common to the Oak Hill Plat and the First Rietz Park Addition, and ~~west~~ went west along the Indian reservation line 145.00 feet to set the witness corner.

**C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:**

On July 28, 1997 I installed a Manistee County Monument, 2" above grade by measuring 145.00 feet from the established East 1/4 corner West along the Indian Reservation line as a careful and faithful witness to the position of the established corner and witnessed by:

1. S 63 E 28.38' 12" Willow
2. N 85 E 21.95' 16" Willow
3. N 52 E 33.50' 14" Willow
4. N 21 E 65.51' 8" Locust



Signed by Anthony M. Slawinski Date 8-4-97  
 Surveyor's Michigan License No. 13597

Corner M-6 WC ratified by the Manistee County Peer Group according to the county plan adopted pursuant to P.A. 345 of 1990, as amended, (being the State Peer Review Form, REG. 261 (1st. seg.)). Date of Peer Review: AUG 05 1997  
*Anthony M. Slawinski*