

LAND CORNER RECORDATION CERTIFICATE
FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

FOR CORNERS OF-- LOCATED IN-- CORNER CODE NUMBER
1. PUBLIC LAND SURVEY T. 22 N. R. 13 W. A-12; A-13
2. PROPERTY CONTROLLING IN SECTION 31 T. 22 N. R. 13 W. 5
3. MISCELLANEOUS PROPERTY IN SECTION T. N. S. R. E. W.
4. LOT NO. , RECORDED PLAT
5. PRIVATE CLAIMS

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, Carl F. Roser do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above (identified with circles on index code diagram - over) were, in a field survey on 6-20 1973, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law.

A. Description of original monument and accessories and/or subsequent restoration:

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

- A-12 Reestablished corner halfway and on line between Fargo corners to N & S.
A-13 Recovered 3/8" spk in B.Top Patch (probably over buried MOn.) that fits U.S.F.S. witnesses; which equals Fargo corner.
5 Established corner per standard B.L.M. instructions.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Table with 3 columns: A-12, A-13, Code 5. A-12: Set DNR MOn & Ced Gd Post, 18" W. Pine S60W 35.11, 21" W. Pine N60W 45.74, 12" W. Oak N35E 16.09. A-13: Found 3/8" spike, 17" W.Oak N52E 64.01, 1" pipe in 6" sq. Con Mon. S45E 47.15, 2" well pipe S20W 140.54, 2" pipe.CPC N45W 46.74. Code 5: Set 1" pipe & Ced post w/loc tag, 6" Maple N62E 28.8', 14" R. Pinr N23W 103.8, NE'ly edge of Tippy Dam Backwater Due W 165'±


SIGNED BY Carl F. Roser DATE 7-16-73

SURVEYOR'S MICHIGAN REGISTRATION NO. 12028

FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY CHIEF OF SURVEY PARTY DATE

APPROVED AND SIGNED BY MICHIGAN REGISTERED LAND SURVEYOR DATE



SURVEYOR'S MICHIGAN REGISTRATION NO.