

**SURVEY & REMONUMENTATION**

DEC 09 1999

**SECTION**

**LAND CORNER RECORDATION CERTIFICATE**  
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

MANISTEE  
(County)

Located In:

Corner Code #

1. Public Land Survey

T 22 N R 14 W  
T 22 N R 13 W  
T \_\_\_\_\_ R \_\_\_\_\_  
T \_\_\_\_\_ R \_\_\_\_\_  
T \_\_\_\_\_ R \_\_\_\_\_  
S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_  
S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_  
S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_  
S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_

M-7  
A-7 ✓

2. Property Controlling in Section

3. Miscellaneous Property in Sec.

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

**REGISTER'S OFFICE**  
**MANISTEE COUNTY**

99-254 at 4:30  
**AUG 12 1999**

*Deborah Dix*  
**REGISTER OF DEEDS**

Register of Deeds Stamp & File Number

I, Sammy S. Barnett, in a field survey on July 7th 19 99, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

**A. Description of original monument and accessories and/or subsequent restoration:**

M - 7 Corner common to sections 13 & 24, T22N, R14W & sections 18 & 19 T22N, R13W

1837 GLO survey by John Brink, set post  
# 1 W. Pine 20" S72W 32 lks (21.12')  
# 2 W. Pine 28" N39 1/2W 23 lks (15.18')

1900 Survey by J.H. Millard, book A, page 94  
mon. not given, found BT's & old stake  
# 3 W.P.stb. 20" S5E 45 lks (29.7')  
# 4 W.P.stb. 26" N23E 67 1/2 lks (44.55')

1909 Survey by Fargo Eng. Co. fd R.R. iron  
& both U.S. Witnesses  
# 5 W. Pine 25" N9W 9 lks (5.94')  
# 6 W. Pine 28" N39 1/2 W 23 lks (15.18')

1977 Survey by R. Griffin fd. R.R. rail 30" long at rd. intersection  
and J. Millard Witnesses, Fargo witnesses gone. set 5" x 36" sq. con mon.  
# 7 W. Oak 12" S57E 53.13'  
# 8 R. Oak 7" N33E 62.50'  
# 9 Maple 9" S15W 53.63'  
# 10 W. Oak 8" S52W 73.24'  
# 11 4" sq. by 7" post South 33.03'

1990 survey by R. Mitchell, Mon. not given, no witnesses given.

**B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:**

M - 7 Corner common to sections 13 & 24, T22N, R14W & sections 18 & 19 T22N, R13W

On July 7th 1999, I found the 5" sq. con. mon. set by R. Griffin, stamped to identify the corner, the condition of the witnesses are as follows Gone # 1, # 2, # 3, # 4, # 5, # 6 & # 11 found in good condition # 7, # 8, # 9 & # 10.

**C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:**

M - 7 Corner common to sections 13 & 24, T22N, R14W & sections 18 & 19 T22N, R13W

On July 7th 1999 I accepted this 5" sq. con. mon as a substantial marker and as a careful & faithful perpetuation of the position of the original corner, & took the following witnesses.

# 7 W. Oak 14" S57E 53.14' fd. 90d spike in SW side  
# 8 R. Oak 14" N33E 62.56' fd. 90d spike in SE side  
# 9 Maple 12" S15W 53.63' fd. 90d spike in SE side  
# 10 W. Oak 10" S52W 73.58' fd. 90d spike in SE side  
# 12 carsonite post South 33'

Corner is in the centerline of E. W. & N. gravel roads.

Corner M-07 ratified by the Manistee County Peer Group according to the county plan adopted pursuant to P.A. 345 of 1990, as amended, (using the State Survey and Remonument Act, MCL 54.261 et seq.). Date of Peer Review: Anthony M. Housseli

AUG 03 1999

Signed by Sammy S. Barnett

Date 8/1/99

Surveyor's Michigan License No. P S # 16923

