

LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

FOR CORNERS OF--:	LOCATED IN--:	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY _____ T. <u>22N</u> N: <u>13W</u> E. _____ S., R. _____ W. _____		K7
2. PROPERTY CONTROLLING IN SECTION _____, T. _____ N: _____ E. _____ S., R. _____ W. _____		
3. MISCELLANEOUS PROPERTY IN SECTION _____, T. _____ N: _____ E. _____ S., R. _____ W. _____		
4. LOT NO. _____, RECORDED PLAT _____		JUL 14 1994
5. PRIVATE CLAIMS _____		COMMISSION

REGISTER'S OFFICE
MANISTEE COUNTY
#94-246 AT 9:55A.M.
JUN 15 1994
Jenny A. Peters
REGISTER OF DEEDS

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, Patrick R. Leemon do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above (identified with circles on index code diagram - over) were, in a field survey on March 30 1994, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on _____ 19____, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. Description of original monument and accessories and/or subsequent restoration:

- | | | |
|---|---|---|
| Section corner common to sections 13, 14, 23 and 24 of T22N R13W | | |
| 1848 survey by Orange Risdon
Set Wood Post
#1 Hemlock 14 N63 1/2 W 27 links
#2 Y.Pine 14 S35E 45 links

1908 survey by E.H. Baird
Fd. old witness trees
#3 Y.Pine Stp. S67E 54 links
#4 W.Pine Stp. 20 S1W 60 links | 1909 survey by Fargo Eng.
Fd. stake & both BT's. Set I.P. w/ lime
#5 W.Pine Stp. 20 S52W 80 links
#6 W.Pine Stp. 24 S85E 31 links

1981 survey by Clinton Cole
#17615 Fd. conc. monu. by Griffin
#8 R.Pine 2 N34E 64.60 feet
#9 Tw.R.Maple 15 S62E 100.17 feet
#10 R.Pine 1 S5E 45.10 feet | #13584
1975 survey by Robert A. Griffin
Fd. I.P. by Fargo Eng. & replaced it with a 5"x36" long conc. monu. with brass cap. Liber 77 Page 37
#7 P.Post 4 North 32.85feet
#8 R.Pine 2 N34E 64.6 feet
#9 Tw.R.Maple 15 S62E 100.17'
#10 R.Pine 1 S5E 45.10 feet |

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:


I found the 5" square by 36" long concrete monument w/ brass cap by Griffin buried 6" beneath the surface on the south edge of an E-W trail road. Witnesses 1 through 6 are gone. Witness 7 through 10 are in good condition. Occupation in the area points to this location. This monument was used in a 1980 survey by Ken Ross #17634 Liber 1 Page 621. This monument is accepted as a careful and faithful perpetuation of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Section corner common to sections 13, 14, 23 and 24 of T22N R13W
Monu. The 5" sq. by 36" long concrete monu. with 3" brass disk was left in place.
Witnesses:
P.Post 4 North 32.88 feet (#7)
R.Pine 9 N34E 64.64 feet (#8)
R.Pine 6 S5E 44.94 feet (10)
B.Oak 4 S34W 104.44 feet
B.Cherry clump 9x6x5 N26W 40.84 feet

Corner K-2 - established by the Manistee County Peer Group according to the county plan adopted pursuant to P.A. 345 of 1990, as amended, (being the State Survey and Remonument Act, MCL 54-261 et seq.). Date of Peer Review: *Patrick R. Leemon* 5/14/94

SIGNED BY *Patrick R. Leemon* DATE April 20 1994
SURVEYOR'S MICHIGAN REGISTRATION NO. 31595



FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY _____ CHIEF OF SURVEY PARTY DATE _____
APPROVED AND SIGNED BY _____ MICHIGAN REGISTERED LAND SURVEYOR DATE _____ (SEAL)

SURVEYOR'S MICHIGAN REGISTRATION NO. _____