

LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, MICH. P.A. 1970

JUL 14 1994
COMMISSION

FOR CORNERS OF--:	LOCATED IN--:	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY _____ T. _____	22N N. 13W E. S., R. W.	M7
2. PROPERTY CONTROLLING IN SECTION _____ T. _____	N. R. E. S., R. W.	
3. MISCELLANEOUS PROPERTY IN SECTION _____ T. _____	N. R. E. S., R. W.	
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER'S OFFICE
MANISTEE COUNTY
#94-250 AT 10:08 A.M.
JUN 15 1994
Penny A. Penner
REGISTER OF DEEDS

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, Patrick R. Leemon do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above (identified with circles on index code diagram - over) were, in a field survey on March 30 1994, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on _____ 19____, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. Description of original monument and accessories and/or subsequent restoration:

Section Cor. com. to sec's. 13 and 24 of T22N R13W and sec's. 18 and 19 of T22N R12W

1837 survey by John Brink Set Wood Post #1 S. Maple 10 S33W 55 links #2 Elm 10 N54W 52 links	1909 survey by Fargo Eng. Fd. wit. #2 & set I.P. w/ lime #3 S. Maple 12 S24W 29 links #4 Hemlock 10 S75 3/4 E 55 links	1976 survey by Robert A. Griffin #13584 Fd. the 10" spike by Cole & replaced it with a 5" square by 36" long conc. monu. with brass cap. #5 P. Post 4 North 32.97 feet #6 "X" cut in top cntr. of west end of conc. hdwl. S76E 88.06 feet #7 NW cor. of House S20E 53.83' #8 "X" in stone 2'x3' S30W 35.28'
	1976 survey by Clinton Cole #17615 Set a spike from Fargo notes No witnesses are mentioned.	

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

I found the 5" square by 36" long concrete monument w/ brass cap by Griffin buried 6" beneath the surface in the centerline of the E-W road. Witnesses 1 through 4 and 5 are gone and witnesses 6 through 8 are in good condition. A 1990 survey by Clinton Cole used this monument and is recorded in Liber 2 Page 170. The GLO calls do not aid in determining this location. There is a lack of good occupation to assist in recovery and I could find no conflicting information that would lead to another location. I talked to the property owner of the house and he did not dispute this location. I therefore accept the found monument as a careful and faithful reestablishment of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Section Cor. com. to sec's. 13 and 24 of T22N R13W and sec's. 18 and 19 of T22N R12W.
Monu. The 5" sq. by 36" long concrete monu. with 3" brass disk was left in place.
Witnesses:
"X" cut in top center of west end of conc. headwall S76E 88.13 feet (#6)
"X" in 2' x 3' stone S30W 35.31 feet (#8)
B. Cherry 17 N31W 111.34 feet
R. Pine 4 N62W 37.00 feet
Tw. R. Oak 28 N69E 132.96 feet

ratified by the Manistee County Peer Group according to the county plan adopted pursuant to P.A. 345 of 1990, as amended, (being the State Survey and Re-enactment Act, MCL 54.261 et seq.). Date of Peer Review: 5/1/94


SIGNED BY *Patrick R. Leemon* DATE April 26, 1994

SURVEYOR'S MICHIGAN REGISTRATION NO. 31595

FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY _____ DATE _____
CHIEF OF SURVEY PARTY

APPROVED AND SIGNED BY _____ DATE _____
MICHIGAN REGISTERED LAND SURVEYOR



(SEAL)

SURVEYOR'S MICHIGAN REGISTRATION NO. _____