

DEC 09 1999

LAND CORNER RECORDATION CERTIFICATE
 Filing Requirement of Act 74, Mich. P.A. 1970

SECTION

For corners in

<u>Manistee</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T <u>22N</u> R <u>15W</u>	<u>M-06 E 1/4 cor. Sec. 13</u>
	T <u>22N</u> R <u>14W</u>	<u>A-06</u> ✓
	T ___ R ___	_____
	T ___ R ___	_____
2. Property Controlling in Section	S ___ T ___ R ___	_____
	S ___ T ___ R ___	_____
3. Miscellaneous Property in Sec.	S ___ T ___ R ___	_____
	S ___ T ___ R ___	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

REGISTER'S OFFICE
MANISTEE COUNTY
 99-331 at 4:25pm
SEP 29 1999
Deborah Dix
REGISTER OF DEEDS

Register of Deeds Stamp & File Number


	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2				
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

I, Bruce J. Jenema, in a field survey on April 29, 19 99 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, reestablished, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

- M-06 T22N R15W (E 1/4 corner Section 13) Common to A-06 T22N, R14W**
- 1837 J. Brink, D.S. GLO
Set Post
1.) 9" Beech S37 1/2°W 29 links (19.14')
2.) 14" Beech N26°W 44 links (29.04')
 - 1909 Fargo Engineering
Rec. C.S. Book A, page 112 & 125
Found Both U.S. Witnesses
Fence 3 directions
Set iron pipe
 - 1914 J.H. Millard, C.S.
Rec. C.S. Book B, pages 194 & 195
Found stake & government bearing trees
3.) 12" Sugar N58°W 17 links (11.22')
 - 1986 USFS corner record Robert Griffen
1 1/4" iron pipe (bent & flattened on end) Fargo iron
Reset-position of iron questionable
No Fargo lime found when reset. Iron had once been removed & replaced upside down
4.) 12" Hard Maple S62°W 71.77' 16d Nail SE side
5.) 6" Hard Maple S65°E 52.99' 16d Nail S side
6.) 5" Hard Maple N73°E 58.73' 16d Nail N side
 - 1995 B.J. Jenema, P.S.
Unrecorded survey Job #95239
Found 1 1/4" O.D. iron pipe



Adopted by the Manistee County Board of Supervisors on 9-16-99
 Rallied by the Manistee County Board of Supervisors on 9-16-99 pursuant to P.A. 345 of 1990, MCL 54.261.
 Date of Filing Review: 9-16-99
 Filing to the County Plan adopted by the State Survey and Reestablishment Act, MCL 54.261.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

On April 29, 1999, I found a 1 1/4" O.D. iron pipe hooked at the base and no lime found 8" below grade. No conflicting evidence of other corners existing.

1.), 2.), 3.), 5.) & 6.) are now extinct.
 4.) 12" Hard Maple S62°W 71.77' Now stump

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

On July 14, 1999, I placed a standard Manistee County Monument in the exact position of the above 1 1/4" O.D. iron and is accepted as the best available evidence of the location of the original corner and witnessed by:

- 4.) 12" Hard Maple S62°W 71.77' 16-D Nail SE side Now stump
- 5.) SE cor. House Block foundation N42°W 163.64'
- 6.) P.pole N10°E 124.91' Set 60-D spike W. side
- 7.) 14" Maple S85°E 51.45' Set 60-D spike S. side
- 8.) 12" B. Locust S90°W 60.48' South 60-D S. side

Signed by Bruce J. Jenema
 Surveyor's Michigan License No. 25850

Date 9-16-99