

SURVEY &
REMONUMENTATION

DEC 09 1999

LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

MANISTEE
(County)

Located In:

Corner Code #

SECTION
REGISTER'S OFFICE
MANISTEE COUNTY

99-252 at 4:20pm
AUG 12 1999

Reborah Dix
REGISTER OF DEEDS

Register of Deeds Stamp & File Number

1. Public Land Survey	T 22N R 14 W	M-2
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, Sammy S. Barnett, in a field survey on June 10th 19 99, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:
M - 2 East one-quarter corner of section 1 T22N, R14W

- | | |
|--|--|
| 1837 GLO survey by John Brink, set post | 1980 survey by K. Ross set 1 1/4" pipe from H. Knight witnesses |
| # 1 Maple 10" S18W 09 lks. (5.94') | # 7 R. Oak 28" N30E 22.43' |
| # 2 Beech 8" 13 1/2W 18 lks (11.88') | # 8 W. Oak 18" S55E 60.63' |
| | # 9 clp. Maple 10" N57W 20.62' |
| 1902 survey by H. Knight, Mon. not given | # 10 W. Oak 18" S38W 20.77' |
| # 3 W.P.S. 28" S14 1/2W 11 lks (7.26') | center of trail North 210' |
| # 4 W.P.S. 24" N13 1/2E 76 lks (50.16') | |
| | 1982 survey by R. Griffin found pipe from Ross witnesses & set a |
| 1935 U.S.F.S., Tech. Passmore Mon. not given | 5" sq x 60" con. mon with a brass cap |
| # 5 W.P.S. 30" South 43.8 lks (28.91') | # 11 Pine post North 2.45' |
| # 6 W.P.S. 20" North 42.2 lks (27.85') | |

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

M - 2 East one-quarter corner of section 1 T22N, R14W
On June 10th 1999 I found the 5" sq con. mon set by R. Griffen, the condition of the witnesses are as follows
Gone 1, 2, remains of stumps 3, 4, 5, 6, in good condition 7, 8, 9, 10, & 11

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

M - 2 East one-quarter corner of section 1 T22N, R14W
On June 10th 1999, I accepted the found 5" square con. mon as a substantial marker and as a careful and faithful reestablishment of the position of the original corner, and took the following witnesses.

- # 7 R. Oak 30" N30E 22.44' fd. 90d spike in SE side
 - # 8 W. Oak 18" S55E 60.62' fd. 90d spike in N side
 - # 9 Maple 14" N57W 20.62' fd. 90d spike in N side
 - # 10 W. Oak 18" S38W 20.76' fd. 90d spike in E side
 - # 11 Pine post North 2.45' fd. nail in E. side
- Corner is approximately 210' south of a graded road on the east side of an area that had been cut over several years ago.

Corner M - 0 2 ratified by the Manistee County Peer Group according to the county plan adopted pursuant to P.A. 345 of 1990, as amended, (being the State Survey and Remonument Act, MCL 54.261 et. seq.). Date of Peer Review: Anthony M. Slavinski

AUG 03 1999

Signed by Sammy S. Barnett Date _____

Surveyor's Michigan License No. P S # 16923

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6	5		4	3			2	1				
3													
4	7	8		9	10			11	12				
5													
6	18	17		16	15			14	13				
7													
8	19	20		21	22			23	24				
9													
10	30	29		28	27			26	25				
11													
12	31	32		33	34			35	36				
13													

