

DEC 09 1999

SECTION \_\_\_\_\_

**LAND CORNER RECORDATION CERTIFICATE**

Filing Requirement of Act 74, Mich. P.A. 1970

|   |                         |               |
|---|-------------------------|---------------|
| For corners in<br><u>MANISTEE</u><br>(County) | Located In:             | Corner Code # |
| 1. Public Land Survey                         | T 22 N R 14 W           | <u>M-8</u>    |
|   | T _____ R _____         | _____         |
|   | T _____ R _____         | _____         |
|   | T _____ R _____         | _____         |
| 2. Property Controlling<br>in Section         | S _____ T _____ R _____ | _____         |
| 3. Miscellaneous<br>Property in Sec.          | S _____ T _____ R _____ | _____         |
| 4. Lot No. _____, Recorded Plat _____         |                         |               |
| 5. Private Claims _____                       |                         |               |

**REGISTER'S OFFICE  
MANISTEE COUNTY**  
99-256 at 4:40 pm  
**AUG 12 1999**  
*Deborah Dix*  
**REGISTER OF DEEDS**

Register of Deeds Stamp & File Number

I, Sammy S. Barnett, in a field survey on June 10th 19 99, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

|    |    |    |    |    |    |    |   |   |   |   |   |   |   |
|----|----|----|----|----|----|----|---|---|---|---|---|---|---|
|    | A  | B  | C  | D  | E  | F  | G | H | I | J | K | L | M |
| 1  |    |    |    |    |    |    |   |   |   |   |   |   |   |
| 2  | 6  | 5  | 4  | 3  | 2  | 1  |   |   |   |   |   |   |   |
| 3  |    |    |    |    |    |    |   |   |   |   |   |   |   |
| 4  | 7  | 8  | 9  | 10 | 11 | 12 |   |   |   |   |   |   |   |
| 5  |    |    |    |    |    |    |   |   |   |   |   |   |   |
| 6  | 18 | 17 | 16 | 15 | 14 | 13 |   |   |   |   |   |   |   |
| 7  |    |    |    |    |    |    |   |   |   |   |   |   |   |
| 8  | 19 | 20 | 21 | 22 | 23 | 24 |   |   |   |   |   |   |   |
| 9  |    |    |    |    |    |    |   |   |   |   |   |   |   |
| 10 | 30 | 29 | 28 | 27 | 26 | 25 |   |   |   |   |   |   |   |
| 11 |    |    |    |    |    |    |   |   |   |   |   |   |   |
| 12 | 31 | 32 | 33 | 34 | 35 | 36 |   |   |   |   |   |   |   |
| 13 |    |    |    |    |    |    |   |   |   |   |   |   |   |

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

**A. Description of original monument and accessories and/or subsequent restoration:**

- M - 8 East one-quarter corner of section 24, T22N, R14W
- |   |  |
|---|--|
| 1837 GLO survey by John Brink, set post<br># 1 Y. Pine 16" S48 1/2W 55 lks (36.3')<br># 2 Y. Pine 17" N43 1/2W 45 lks (29.7')                               | 1977 survey by R. Griffin fd. 1" x 30" pipe from GLO. Millard & Fargo witnesses, set 5" x 60" con. mon. with a brass cap.<br># 6 Maple 10" N65W 21.41'<br># 7 R. Oak 10" N17W 25.56'<br># 8 4" sq. x 7' post North 1.30' |
| 1900 survey by J. Millard, book A page 94<br>fd old pt. of stake<br># 3 W. Pine 28" N6W 8 lks (5.28')<br># 4 Y. Pine no size N53 1/2W 45 lks (29.7')        | 1983 survey by A. Slawinski, mon. not given. no new witnesses  |
| 1909 survey by Fargo Eng. Co set 1" x 30" pipe<br>from GLO & Millard witnesses<br># 3 W. Pine stp. N9W 9 lks (5.94')<br># 5 Y. Pine 8" S27W 48 lks (31.68') | 1990 survey by R. Mitchell, mon. not given, no witnesses given   |

**B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:**

M - 8 East one-quarter corner of section 24, T22N, R14W  
On June 10th 1999, I found the con. mon. set by R. Griffin, the condition of the witnesses are as follows.  
Gone 1, 2, 3, 4, & 5 Found in good condition 6, 7 & 8

**C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:**

M - 8 East one-quarter corner of section 24, T22N, R14W  
On June 10th 1999 I accepted the found 5" sq. con. mon. as a substantial marker and is accepted as a careful and faithful perpetuation of the position of the original corner, and took the following witnesses.  
# 6 Maple 12" N65W 21.41' fd. 90d spike in NE side  
# 7 R. Oak 12" N17W 25.56' fd 90d spike in W side  
# 8 4"sq. x 7' post N 1.3' no nail  
# 9 5" sq. con. mon with brass cap S. 33.00' Indian reserve line  
# 10 R. Oak 12" S67W 15.95' set 60d spike in N. side  
Corner is in line with 2 track to N. & approximately 100' north and 100' W. of 2 track

Corner M-08 ratified by the Manistee County Peer Group according to the county plan and rules set in P.A. 945 of 1990, as amended, (being the State Survey and Monumentation Act, MCL 54.261 et seq.). Date of Peer Review: AUG 03 1999  
*Anthony M. Slawinski*



Signed by Sammy S. Barnett Date 8/1/99  
Surveyor's Michigan License No. PS # 16923