

SURVEY & REMONUMENTATION

DEC 6 1999

LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. P.A. 1970

SECTION

For corners in <u>MANISTEE</u> <small>(County)</small>	Located In:	Corner Code #	
1. Public Land Survey	T 22 N R 14 W T 22 N R 13 W T _____ R _____ T _____ R _____	<u>M-9</u> ✓ <u>A-9</u>	
2. Property Controlling in Section	S _____ T _____ R _____ S _____ T _____ R _____		
3. Miscellaneous Property in Sec.	S _____ T _____ R _____ S _____ T _____ R _____		
4. Lot No. _____, Recorded Plat _____			
5. Private Claims _____			

**REGISTER'S OFFICE
MANISTEE COUNTY**
99-257 at 4:45pm
AUG 12 1999
Deborah Sue
REGISTER OF DEEDS

Register of Deeds Stamp & File Number

I, Sammy S. Barnett, in a field survey on June 10th 19 99, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:
M - 9 Corner common to sections 24 & 25 T22N, R14W & sections 19 & 30 T22N, R13W

- | | |
|---|---|
| <p>1837 GLO survey by John Brink, set post
1 Y. Pine 16" S10W 47 lks (31.02')
2 W. Pine 12" N52 1/2W 56 lks (36.96')</p> <p>1900 survey by J. Millard, fd. both bt's & stake
3 W. Pine stp. 18" S85E 18 lks (11.88')
4 W. Pine 20" N54 1/2E 11 1/2 lks (7.59')</p> <p>1909 survey by Fargo Eng. Co. fd. Millards witnesses & set 1" x 30" pipe
4 W. Pine stp. 16" S85 3/4E 17 3/4 lks (11.72')
5 W. Pine stp. 20" N50 1/4E 11 lks (7.26')</p> | <p>1972 USFS tech. House fd. 1" Fargo pipe under 2" C.P. capped pipe, witnesses old but ok.
6 R. Oak 3" S62W 5.05'
7 W. Pine 4" S40E 10.65'
8 R. Maple 3" N48E 21.80'</p> <p>1973 survey by C. Roser fd pipe & checked USFS witnesses</p> <p>1983 survey by A. Slawinski, fd pipe
9 Pine 6" S10E 10.53'
10 Maple 8" West 4.94'</p> <p>1990 survey by R. Mitchell fd. pipe & set 2" x 30" brass capped pipe
10 R. Maple 9" S56W 4.92'
8 R. Maple 7" N41E 21.59'
11 R. Maple 10" East 33.60'
12 R. Oak 8" S10E 13.68'
13 Carsonite post West 3.0'</p> |
|---|---|

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
M - 9 Corner common to sections 24 & 25 T22N, R14W & sections 19 & 30 T22N, R13W
On June 10th 1999, I found the brass capped pipe set by Mitchell, the condition of the witness are as follows. Gone 1, 2, 3, 4, 5, 6 & 9, found in good condition 7, 8, 10, 11, 12 & 13

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
M - 9 Corner common to sections 24 & 25 T22N, R14W & sections 19 & 30 T22N, R13W
On June 10th 1999, I accepted the found brass capped pipe as a substantial marker and as a careful and faithful perpetuation of the position of the original corner, and took the following witnesses.

- # 7 W. Pine 6" S40E 10.60' fd. 16d spike in W. side
- # 8 Maple 8" N47E 21.57' fd. 60d spike in NW side, Blazed & scribed
- # 10 Maple 10" S65W 4.94' fd. 60d spike in S. side, Blazed & scribed
- # 11 R. Maple 10" East 33.60' fd. 60d spike in S. side
- # 12 R. Oak 8" S10E 13.68' fd. 60d spike in W. side
- # 13 Carsonite post West 3.0 ft.

Corner M-9 verified by the Manistee County Peer Group according to the county plan adopted pursuant to P.A. 345 of 1980, as amended, (being the Cross Survey and Remonument Act, MCL 56261 et seq.). Date of Peer Review: AUG 03 1999

Signed by Sammy S. Barnett Date 8/1/99
Anthony M. Slawinski

Surveyor's Michigan License No. PS # 16923

