

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

<u>MANISTEE</u> (County)	Located In:	Corner Code: #
1. Public Land Survey	T 22 N R 16W	F-3
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

REGISTER'S OFFICE
MANISTEE COUNTY
95-351 at 1:25pm
SEP - 7 1995
Deborah Six Sep.
REGISTER OF DEEDS

Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, John Schulke, in a field survey on July 7th, 1995, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

In 1839, J. Brink set a wooden post with the following corner references: 1. Beech 8" N 2 1/2°E 12 links.
 2. Beech 10" S39°W 13 links.

In 1904, Harrison Knight (County Surveyor) set a cedar stake and buried an old ax head and stones in the road in line with fences running North & South.
 No references.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

May 14, 1994, I recovered an ax head with stones around it in an abandoned East-West road. Old fence running South and also old fences running East and West on both sides of road. A ridge running North 150 feet ±. Set 3/4"X18" capped iron pipe in place of axe head and placed the axe head along side the pipe. The following corner references:

- 3. R Oak 19" N25°E 37.21 ft.
- 4. Beech 18" South 17.62 ft.
- 5. Sug. Maple 22" S52°E 11.22 ft.
- 6. Beech 16" N43°W 23.25 ft.
- 7. 1/2" iron Rod N21°W 15.98 ft.

NOTE: The monument is on the Eastern slope of a hill.

NOTE: The ridge looks like it was caused by an old fence line.

July 7, 1995, found capped iron, axe head and stones. Found the following corner references listed above except 1, 2, and 7.

Distances to the following corners:

- E-3 (Northwest corner of Sec. 9) 2623.20 ft. by Schulke & Jenema
- F-2 (Center 1/4 corner of Sec. 4) 2645.30 ft. by Jenema
- G-3 (Northeast corner of Sec. 9) 2616.82 ft. by Schulke

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Accepting the above evidence as being perpetuated location of the Government corner, I replaced the 3/4" iron pipe with 2" dia. X30" galvanized pipe monument with brass cap stamped to identify the corner. Placed old axe head on North side of monument and placed the stones around the monument. The following corner references:

- 3. R Oak 19" N25°E 37.25 ft.
- 4. Beech 18" South 17.69 ft.
- 5. Sug. Maple 22" S53°E 11.21 ft.
- 6. Beech 16" N42°W 23.25 ft.

NOTE: All BT's blazed and scribed with a 60-D spikes.

Corner _____ ratified by the Manistee County Peer Group according to the county plan adopted pursuant to P.A. 345 of 1990, as amended, (being the State Survey and Remonument Act, MCL 54.261 et. seq.). Date of Peer Review: SEP 5 1995



Signed by John C. Schulke Date July 31, 1995

Surveyor's Michigan License No. RLS-30894