

MAY 16 1997

COMMISSION

LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

<u>MANISTEE</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T 22 N R 16 W T 22 N R 15 W T _____ R _____ T _____ R _____	M-06 ✓ A-06
2. Property Controlling in Section	S _____ T _____ R _____ S _____ T _____ R _____	
3. Miscellaneous Property in Sec.	S _____ T _____ R _____ S _____ T _____ R _____	

REGISTER'S OFFICE  
MANISTEE COUNTY

#96-300 AT 9:57 A.M.  
JUL 17 1996

*Penny A. Peasa*  
REGISTER OF DEEDS

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, Sammy S. Barnett, in a field survey on May 14, 1996, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

M-06 East 1/4 Corner for Section 13, T22N, R16W., on the Township Line

*JOHN*  
Brink, 1837, G.L.O. boundary survey #4 Hemlock Stump 16" S23°E 106½lks. (70.29')

Set Wood Post  
#1 Sugar 11" S56°W 48lks. (31.68') Sammy S. Barnett RLS#16923, 1984  
#2 Beech 10" N65°W 44lks. (29.04') Found Iron  
L. 1, Pg. 787

John Millard, 1897, MCS  
Set Stone & Iron, old corner lost M.C.R.C., 1985  
#3 Beech 7" S51°E 138½/21lks. (91.41') Found "T" Iron, from field notes

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

M-06 East 1/4 corner for Section 13, T22N, R16W, on the Township Line

On May 14, 1996, I found a "T" Iron at the Intersection of Milarch Road & Coates Hwy., I found no evidence to dispute this location for the 1/4 corner.

Condition of recorded witnesses are;

- #1 Gone
- #2 Gone
- #3 Gone
- #4 gone

Corner M-06 ratified by the Manistee County Peer Group according to the county plan adopted pursuant to P.A. 345 of 1990, as amended, (being the State Survey and Remonument Act, MCL 54.261 et seq.). Date of Peer Review: JUL 2 1996

*Anthony M. Slain*

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

M-06 East 1/4 corner for Section 13, T22N, R16W, on the Township Line

I replaced "T" Iron, in the exact location, with a Standard Manistee County Monument, .5 feet below the road surface, inside a new road monument box, and is accepted as a careful and faithful reestablishment of the position of the original corner.

- Power Pole S 40° W 55.38' (60d spike in SW side of pole)
- Survey Marker 1" stamped brass rod N 38° E 33.78' (flush w/ road surface)
- EBP (GBT) Power Pole N 52° W 79.95' (16p w/ shiner in NE side of pole)
- EBP (GBT) Power Pole N 32° W 54.00' (16p w/ shiner in NE side of pole)

Signed by Sammy S. Barnett  
Surveyor's Michigan License No. 16923

Date 6-26-96

