

# LAND CORNER RECORDATION CERTIFICATE

## FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

FOR CORNERS OF --	LOCATED IN --	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY <u>22</u>	T. <u>22</u> N. <u>17</u> W.	M-10; M-11
2. PROPERTY CONTROLLING IN SECTION <u>25</u>	T. <u>22</u> N. <u>17</u> W.	16
3. MISCELLANEOUS PROPERTY IN SECTION <u>25</u>	T. <u>22</u> N. <u>17</u> W.	XX (508.66' W of L-10 on line M-10, L-10 extended)
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, Carl F. Roser do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above (identified with circles on index code diagram - over) were, in a field survey on 12/06/1974, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on 12-6 1974, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

~~A. Description of original monument and accessories and/or subsequent restoration:~~

C. (continued)

XX		
Set 1 1/4" x 36" pipe & cedar post w/loc. tag		
8" Spruce	N22°W	7.49
6" Spruce	N75°E	20.55
12" Apple	S01°E	90.80
Top edge of bluff	Due W	32

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

- M-10 Found axle shaft; old accepted corner of record.
  - M-11 Found 3/8" rerod; old accepted corner of record.
  - 16 Established SE corner of SW 1/4 of SE 1/4 of Sec. 25, equidistant and on line between recovered SE and S 1/4 of Sec. 25.
  - XX Established point on E-W 1/4 line, 508.66' west of center of Sec. 25, on line extended from E 1/4, S-25 through center of S-25.
- C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

M-10	M-11	16
Found axle shaft	Found rerod & added 1"x18" iron rod	Set 1"x36" pipe & ced. post w/loc. tag
14" Oak S45°W 46.49	26" Oak S53°E 34.00	8" Oak N04°W 76.5
20" Beech N40°W 36.07	12" Oak S74°W 51.40	10" R. Pine N41°W 93.7
12" Hemlock S39°E 61.49	12" Oak N35°E 65.55	7" R. Pine S64°W 57.7
set ced. post w/loc. tag Due W 33	set ced. post w/loc. tag Due W 33	Old Fence Corn. S82°W 14.2
Ctr. N-S blacktop county road Due E 2.5	Ctr. N-S blacktop county road Due E 1'	


SIGNED BY Carl F. Roser 2-20-75 DATE \_\_\_\_\_

SURVEYOR'S MICHIGAN REGISTRATION NO. 12028

FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY \_\_\_\_\_ DATE \_\_\_\_\_  
CHIEF OF SURVEY PARTY

APPROVED AND SIGNED BY \_\_\_\_\_ DATE \_\_\_\_\_  
MICHIGAN REGISTERED LAND SURVEYOR



MANISTEE TOWNSHIP (N.P.)  
 MANISTEE COUNTY

SURVEYOR'S MICHIGAN REGISTRATION NO. \_\_\_\_\_