

DEC 09 1999

SECTION LAND CORNER RECORDATION CERTIFICATE
 Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

<u>Manistee</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T <u>22N</u> R <u>17W</u>	<u>M-08</u>
	T _____ R _____	<u>East 1/4 Cor.</u>
	T _____ R _____	<u>Sec. 24</u>
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

REGISTER'S OFFICE
 MANISTEE COUNTY

99-222 at 1:20pm
 JUL 22 1999

Deborah Six
 REGISTER OF DEEDS

Register of Deeds Stamp & File Number

I, Anthony M. Slawinski, in a field survey on May 5, 19 99 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:
 M-08 East 1/4 Corner, Section 24, T22N, R17W

Set by John Brink in 1837

- 1. Aspen 8" dia. S 49° W 31 links (20.46') (Gone)
- 2. Birch 10" dia. N 63 1/2° W 07 links (4.62') (Gone)

County Surveyor Notes by J.H.M. in 1900

- Fd. Stake & Roots of a B.T.
- 3. White Pine 24" S 52° W 128 links (84.48') (Gone)
- 4. White Pine 3" N 87° W 116 links (76.56') (Gone)

Plat of Oak Park Beach, 1913
 Liber 3 of plats, Page 12
 (NE. Plat corner is M-08)

Field Notes by Slawinski, 1967
 Found 1 1/2" iron pipe

- 5. Northwest 45.28' 10" White Pine (Good)
- 6. Northeast 75.06' 6" Birch (Gone)
- 7. Southeast 86.65' 10" Maple (Gone)
- 8. Southwest 97.27' 12" Pine (Gone)

Survey Map by Bruning, 1977 (No w/ths)

Survey Certificate by Slawinski, 1989 (No w/ths)

Survey Certificate by Slawinski, 1990 (No w/ths)
 Found 1 1/2" Iron pipe

- Field Notes by Ross 1996
- Fd. 1" iron pipe
- 9. S 72° E 14.13' 12" R. Pine (Good)
- 5. N 45° W 45.90' 16" R. Pine (Good)
- 10. S 30° E 12.74' Power Pole (Gone)
- 11. N 51° E 44.49' 14" W. Pine (Good)

Field Notes by Abonmarche, 1999

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
 M-08 East 1/4 Corner, Section 24, T22N, R17W

On May 5, 1999, I Anthony Slawinski, along with a field crew from Abonmarche Found a 1 1/2" Iron pipe that measured 37" in length. A 1" Iron pipe measuring 17" in length was also found 0.25' to the Southeast of the above mentioned 1 1/2" Iron pipe. The 1 1/2" pipe was considerably deeper in the ground than the 1" pipe, and the 1 1/2" pipe is the one I used in 1967. At that time the 1" pipe was not present. I accepted the 1 1/2" Iron Pipe as the corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
 M-08 East 1/4 Corner, Section 24, T22N, R17W

On May 5, 1999, I installed a Manistee County Monument in the exact location of the above mentioned 1 1/2" Iron pipe as a careful and faithful re-establishment of the position of the original corner and witnessed by:

- 5. N 43° W 45.54' 17" Red Pine, found 60D Spike on the Southwest side of tree
- 9. S 76° E 14.25' 12" Red Pine, found 60D spike on the North side of tree
- 11. N 51° E 44.40' 15" White Pine, found 60D spike on the Northwest side of tree
- 12. N 09° W 58.67' 8" Maple, set 60D spike on the Northeast side of tree

Note: Corner is on the centerline of Poplar Road extended East. ±1' East off from asplan

Signed by Anthony M. Slawinski
 Surveyor's Michigan License No. 13597



Date 7-2-99

STATE BOARD OF PROFESSIONAL SURVEYORS, JAN. 28, 1971
 REVISED MAY 14, 1975
 REVISED JAN., 1983
 REVISED OCT., 1995

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6			5			4			3			1
3													
4	7			8			9			10			12
5													
6	18			17			16			15			13
7													
8	19			20			21			22			24
9													
10	30			29			28			27			25
11													
12	31			32			33			34			36
13													

ratified by the Manistee County Peer Group according to the county plan adopted pursuant to P.A. 345 of 1999, as amended, (Using the State Survey and Remonument Act MCL 54.251 et. seq.) . Date of Peer Review: Anthony M. Slawinski

JUL 6 1999