

RENEW SURVEY & SECTION

MAY 03 2000

LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

<u>Manistee</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T <u>22N</u> R <u>17W</u>	M-09 ✓
	T _____ R _____	Southeast Sec.
	T _____ R _____	Cor. Sec. 24
	T _____ R _____	
2. Property Controlling in Section	S _____ T <u>22N</u> R <u>17W</u>	M-19
	S _____ T _____ R _____	
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	
	S _____ T _____ R _____	
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

REGISTER'S OFFICE  
MANISTEE COUNTY

99-219 at 1:05pm  
JUL 22 1999

Deborah Six  
REGISTER OF DEEDS

Register of Deeds Stamp & File  
Number

I, Anthony M. Slawinski, in a field survey on May 5, 19 99 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	10		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:  
M-09 Southeast Section Corner Section 24, T22N, R17W

- Set by John Brink in 1837
- 1. Beech 10" dia. S 34½° W 30 links (19.80') (Gone)
- 2. Beech 8" dia. N 44° W 26 links (17.16') (Gone)

- County Surveyor Notes by Manchester 1940
- Fd. Fence corner & Beech Stump at corner
- 3. Beech 8" Southwest 88 links (58.08') (Gone)

- Survey Certificate by Slawinski 1976
- Found 1" iron pipe
- 4. S 45° W 44.92' 7" Poplar (Stump was found, but tree has died and fallen)
- 5. N 45° W 68.65' 6" W. Pine (Good tree is now 27" in diameter)

Survey Map by H.R. Bruning 1977 (No Witnesses)  
Field Notes by Abonmarche, 1999

- Field Notes by Ross 1996
- Fd. 1½" pipe
- 5. NW 68.67' 8" W. Pine (Good)
- 6. SW 28.26' 4" Triple Ash (Gone)
- 7. SE 36.61' Power Pole (Good)
- 8. NE 64.35' End 12" CMP (Good)
- 9. E 58.89' End 12" CMP (Good)

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:  
M-09 Southeast Section Corner Section 24, T22N, R17W

On May 5, 1999, I, Anthony Slawinski, along with a field crew from Abonmarche, found a 1" Iron Pipe. I found no other evidence to dispute this location for the corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:  
M-09 Southeast Section Corner Section 24, T22N, R17W

On May 5, 1999, I installed a Manistee County Monument in the exact location as the above mentioned 1" Iron Pipe, as a careful and faithful re-establishment of the position of the original corner and witnessed by:

- 5. N 45° W 68.65' 27" White Pine, found 60D spike on the Northeast side of tree
- 7. S 49° E 36.48' Power Pole, found Double Headed nail on the Northeast side of pole
- 10. S 37° W 17.36' 16" Oak, set 60D spike on the Northwest side of tree
- 11. N 06° E 70.88' 24" Ash, set 60D spike on the East side of tree

Note: The corner is ±1' South of the South edge of Birch Road.

Signed by Anthony M. Slawinski  
Surveyor's Michigan License No. 13597



Date 7-2-99

Corner M-09  
according to the county plan submitted to the Board of 645 of 1990,  
as amended, (being the State Survey and Monument Act, 1974, §4.261  
et seq.). Date of Peer Review: Anthony M. Slawinski

JUL 6 1999