

DEC 28 1998

SECTION

LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

Manistee (County) Located In: Corner Code #
1. Public Land Survey T 22N R 17W M-11 Southeast Sec. Cor. Sec. 25 A-11
2. Property Controlling in Section S T R
3. Miscellaneous Property in Sec. S T R
4. Lot No. Recorded Plat
5. Private Claims

REGISTER'S OFFICE MANISTEE COUNTY

98-281 at 4:50pm JUL 10 1998

REGISTER OF DEEDS

Register of Deeds Stamp & File Number

I, Anthony M. Slawinski, in a field survey on June 30, 19 98 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

Set by John Brink in 1837

- 1. White Pine 12" S 25° W 30 links (Gone)
2. Black Oak 12" N 64 W 36 links (Gone)

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Information Referenced:

- County Surveyor Notes by Millard (1900) Survey Certificate by Roser (1975)
County Surveyor Notes by Manchester (1936) Survey Certificate by Slawinski (1984)

L.C.R.C. by Roser (1975)

found rerod & added 1"x18" iron rod

- 3. S 53° E 34.00 26" Oak (Good)
4. S 74° W 51.00' 12" Oak (Gone)
5. N 35° E 65.55' 12" Oak (Good)
6. West 33' Set Cedar post w/Loc. Tag (Gone)
7. East 1' Center of blacktop

On March 20, 1998, I Anthony Slawinski, along with Abonmarche found a 1" iron rod approximately 1' west of center line of Hill Road.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

On June 30, 1998, I installed a Manistee County Monument, within a monument box, in the exact location as the above mentioned 1" iron rod, as a careful and faithful re-establishment of the position of the original corner and witnessed by:

- 3. S 50° E 33.95' 30" Oak, 60D spike in the North Side
5. N 30° E 65.28' 21" Oak, 60D spike in the South side
8. S 41° E 54.99' 8" Black Oak, 60D spike in the Southwest side
9. S 67° W 55.74' 12" White Oak, 60D spike in the Southeast side

Note: North 2846.20 feet to the East 1/4 Corner of Section 25, T22N., R17W.



Corner M-11 ratified by the Manistee County Peer Group according to the county plan adopted pursuant to P.A. 345 of 1990, as amended, (being the State Survey and Remonument Act, MCL 54.261 et. seq.). Date of Peer Review JUN 2 1998

Anthony M. Slawinski

Signed by Anthony M. Slawinski

Date 6-30-98

Surveyor's Michigan License No. 13597

Grid table with columns A-N and rows 1-13. Numbers 1-36 are placed in specific cells: 6, 5, 4, 3, 2, 1 in row 2; 7, 8, 9, 10, 11, 12 in row 4; 18, 17, 16, 15, 14, 13 in row 6; 19, 20, 21, 22, 23, 24 in row 8; 30, 29, 28, 27, 26, 25 in row 10; 31, 32, 33, 34, 35, 36 in row 12.