

MAY 16 1997

COMMISSION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

MANISTEE (County)	Located In:	Corner Code #
1. Public Land Survey	T 22N R 16W N 2 T 22N R 15W A 2	
2. Property Controlling in Section	S T R	
3. Miscellaneous Property in Sec.	S T R	

REGISTER'S OFFICE
MANISTEE COUNTY
96-302 AT 10:05 A.M.
JUL 17 1996
Penny A. Repora
REGISTER OF DEEDS

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, Sammy S. Barnett, in a field survey on June 21, 1996, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

A. Description of original monument and accessories and/or subsequent restoration:

M-2 East 1/4 Corner for Section 1, T22N, R16W, On the Township Line

1837, John Brink, D.S., G.L.O.

Set Wood Post @ 40 chains

#1 Beech 11" S72W 46 lks

#2 Beech 10" N21W 58 lks

1910, E.W. Muenschler

Found Stake by Hubble ("book A", pg. 124)

#3 White Pine Stump 24" N33 1/2°E 95lks. 62.70'

1974, Dan Verba, RLS #13603

Found "PK nail" in C-L of

C & O RR tracks, set by Tony Slawinski, RLS #13957.

#4 Power Pole N40°W 46.28'

#5 Power Pole N69°E 116.34'

#6 Fence Cor. Post S42°W 66.02'

1984, L. Gerschbacher, RLS #185

States that Corner was destroyed with the removal of Railroad track. Reset 3/4" Pipe with a 5/8" x 2 Re-bar w/ RLS cap from old Iron

1994 A. Slawinski L 2 P 560

No witnesses

B. Jennera file 88318

No witnesses

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

M-2 East 1/4 Corner for Section 1, T22N, R16W, On the Township Line

On June 21st 1996 I found 1/2" X 18" capped re-bar 1' West of centerline of Milarch Rd. in centerline of old grade East-West

All old witnesses are gone.

Corner M - 02 ratified by the Manistee County Peer Group according to the county plan adopted pursuant to P.A. 345 of 1990, as amended, (being the State Survey and Remonument Act, MCL 54.261 et. seq.). Date of Peer Review: JUL 2 1996

Anthony M. Slawinski

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

M-2 East 1/4 Corner for Section 1, T22N, R16W, On the Township Line

On June 21, 1996, I Replaced 1/2" Re-rod with a RLS cap 18" long, in the exact location with a Standard Manistee County Monument, 0.5 feet below road surface, inside a road monument box, and is accepted as a careful and faithful reestablishment of the position of the original corner.

(OBT) Red Pine 12" S 45° E 81.45' (60d spike in NE side of tree)

(OBT) Sassafras 5" N 35° E 69.85' (60d spike in NW side of tree)

Iron Pipe 1" RLS #13603 S 85° E 33.00'

Yellow Gate Post 2" Steel S 87° W 169.87'

Signed by *Sammy S. Barnett*

Date 6-26-96

Surveyor's Michigan License No. 16923

