

SURVEY &
REMONUMENTATION

MAY 16 1997

COMMISSION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

<u>MANISTEE</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T 22 N R 16 W	M-06
	T <u>22N</u> R <u>15W</u>	<u>A-6</u>
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

REGISTER'S OFFICE
MANISTEE COUNTY

#96-300 AT 9:57 A.M.

JUL 17 1996

Penny A. Pease
REGISTER OF DEEDS

Register of Deeds Stamp & File Number

I, Sammy S. Barnett, in a field survey on May 14, 19 96, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

M-06 East 1/4 Corner for Section 13, T22N, R16W., on the Township Line

JOHN

Brink 1837, G.L.O. boundary survey #4 Hemlock Stump 16" S23°E 106½lks. (70.29')

Set Wood Post

#1 Sugar 11" S56°W 48lks. (31.68')

#2 Beech 10" N65°W 44lks. (29.04')

John Millard, 1897, MCS

Set Stone & Iron, old corner lost

#3 Beech 7" S51°E 138½/21lks. (91.41')

Sammy S. Barnett RLS#16923, 1984

Found Iron

L. 1, Pg. 787

M.C.R.C., 1985

Found "T" Iron, from field notes

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

M-06 East 1/4 corner for Section 13, T22N, R16W, on the Township Line

On May 14, 1996, I found a "T" Iron at the Intersection of Milarch Road & Coates Hwy., I found no evidence to dispute this location for the 1/4 corner.

Condition of recorded witnesses are;

- #1 Gone
- #2 Gone
- #3 Gone
- #4 gone

Corner M-06 ratified by the Manistee County Peer Group according to the county plan adopted pursuant to P.A. 345 of 1990, as amended, (being the State Survey and Remonument Act, MCL 54.261 et seq.). Date of Peer Review: JUL 2 1996

Anthony M. Slawinski

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

M-06 East 1/4 corner for Section 13, T22N, R16W, on the Township Line

I replaced "T" Iron, in the exact location, with a Standard Manistee County Monument, .5 feet below the road surface, inside a new road monument box, and is accepted as a careful and faithful reestablishment of the position of the original corner.

Power Pole S 40° W 55.38' (60d spike in SW side of pole)

Survey Marker 1" stamped brass rod N 38° E 33.78' (flush w/ road surface)

EBP (EBT) Power Pole N 52° W 79.95' (16p w/ shiner in NE side of pole)

EBP (EBT) Power Pole N 32° W 54.00' (16p w/ shiner in NE side of pole)

Signed by Sammy S. Barnett

Date 6-26-96

Surveyor's Michigan License No. 16923

