

REMOVAL

MAY 15 1997

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

Table with columns: MANISTEE (County), Located In:, Corner Code #. Rows include Public Land Survey, Property Controlling in Section, and Miscellaneous Property in Sec.

REGISTER'S OFFICE
MANISTEE COUNTY
#94399 AT 9:55 A.M.
JUL 17 1996
Penny A. Pepera
REGISTER OF DEEDS

Register of Deeds Stamp & File Number

4. Lot No. , Recorded Plat
5. Private Claims

I, Sammy S. Barnett, in a field survey on May 28, 1996, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

B-03 South 1/4 Corner for Section 6, T22N, R15W.

John Brink, 1839, G.L.O.

E.W. Muenschler, 1910

Danny Bongiovanni, RLS #24586 1981

Set Wood Post

Set Stake & Stone, from testimony from Johnson
No new witnesses

Found 3/4" Iron Iron #3 Power Pole South 69.35'

- #1 Beech 7" N 06° E 15 lks.(9.90')
#2 Beech 7" S 10° W 15 lks.(9.90')

1988, B. Jenema
Found Iron Pipe

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

B-03 South 1/4 Corner for Section 6, T22N, R15W.

On May 28, 1996, I found a 60d spike over a 1" iron Pipe, next to a 1 1/4" Iron pipe 1 foot below the surface of the road, I found no other evidence to disputed this location for the 1/4 corner, note Kerry Road has been filled, substantially.

Condition of recorded witnesses are;

- #1 Gone
#2 Gone
#3 Found in good condition

Corner B-03 ratified by the Manistee County Peer Group according to the county plan adopted pursuant to P.A. 345 of 1990, as amended, (being the State Survey and Remonument Act, MCL 54.261 et. seq.). Date of Peer Review: [Signature]

JUL 2 1996

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

B-03 South 1/4 corner for Section 6, T22N, R15W.

I replaced both Iron Pipes, in the exact location with a Standard Manistee County Monument, place inside a new road monument box. And is accepted as a careful and faithful reestablishment of the position of the original corner.

- (OBJ #3) Power pole S 03° E 69.44'(16p D.H. Nail w/ shiner in East side of pole)
Power Pole N 28° W 158.65'(60d spike in NE side of pole)
Litter fine sign S 77° W 63.53'
Set 1 1/4" Iron Pipe for witness, N 41° E 23.88'

Signed by [Signature]

Date 6-26-96

Surveyor's Michigan License No. 16973

