

DEC 11 1999

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in SECTION

Manistee (County) Located In: Corner Code #
1. Public Land Survey T 22N R 15W M-03 SE cor. Sec. 1
T 22N R 14W A-03
2. Property Controlling in Section S T R
3. Miscellaneous Property in Sec. S T R
4. Lot No. Recorded Plat
5. Private Claims

REGISTER'S OFFICE MANISTEE COUNTY
99-330 at 4:20pm
SEP 29 1999
REGISTER OF DEEDS

Register of Deeds Stamp & File Number
Grid with columns A-M and rows 1-13. Cell 3,3 contains a black dot.

I, Bruce J. Jenema, in a field survey on April 27, 19 99 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, reestablished, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

M-03 T22N, R15W (SE corner Sec. 1) Common to A-03 T22N, R14W


1837 J. Brink, D.S. GLO
Set Post
1.) 10" Hemlock S36°W 16 links (10.56")
2.) 12" Elm N62 1/2°W 16 links (10.56")

1900 J.H. Millard
County Survey Bk A, pg 106&119 and Bk B pg 34 & 35
Found Stake and Government bearing trees

1901 H.E. Knight, D.S.
County Survey Book B, pages 90-91
1.) 16" Hemlock S36°W 16 links (10.56")
2.) 20" Elm N62 1/2°W 16 links (10.56")
Elm laying on ground & Hemlock bears old blaze marks of T22N, R15W

Manistee County Road Commission
"P.I."
3.) P. Pole North 32.02'
4.) Tacked stake SE 100.00'

9/10/1992 A.M. Slawinski
NE corner Section 12 22-15
Found 3/4" Iron Rod
3.) P. Pole North 32.02' roofing nail & cap in face
6.) P.pole N25°W 39.24'
7.) P. pole S30°W 36.60'
8.) 14" W. pine S60°E 106.05'



B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

On April 27, 1999, I found a 3/4" iron rod. No conflicting evidence of other corners existing.
Witnesses 1,2,3,4 are now extinct.
Found witness 6.), 7.), 8.) in good condition.
Fence line running North.
Corner is located 7' South & 8' West of apparent centerline intersection of Johnson E-W Road & Leckrone Road South.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

On July 14, 1999, I place a standard Manistee County Monument in the exact position of the above 3/4" iron rod and is accepted as the best available evidence of the position of the original corner and witnessed by:
6.) N25°W P.Pole 39.20' Found nail & watch gear East side
7.) S30°W P.Pole 36.59' Found nail & watch gear East side
8.) S66°E 16" W. Pine 106.35' Found nail & watch gear North side
9.) S20°E 14" Poplar 93.30' Set 60-D spike East side

ratified by the Manistee County Peer Group according to the county plan adopted pursuant to P.A. 345 of 1990, as amended, (being the State Survey and Remonument Act, MCL 54.261 et. seq.). Date of Peer Review: Sept 7, 1999

Signed by Bruce J. Jenema
Surveyor's Michigan License No. 25850

Date 9-16-99