

MAY 16 1997

COMMISSION

LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

MANISTEE (County)	Located In:	Corner Code #
1. Public Land Survey	T <del>22N</del> R <del>16W</del>	Indian Reserve
	T _____ R _____	M-881
	T _____ R _____	OTHER CODE #1
	T <u>22N</u> R <u>15W</u>	INDIAN RESERVE A-81
2. Property Controlling in Section	S _____ T _____ R _____	OTHER CODE #2
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	

REGISTER'S OFFICE  
MANISTEE COUNTY

#96-304 AT 10:15 A.M.

JUL 17 1996

*Penny A. Piper*  
REGISTER OF DEEDS

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

I, Sammy S. Barnett, in a field survey on May 6, 1996, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

M-08 I Indian Reserve Corner, T22N, R16W, on East Township Line 1991 Jenena same as Gerschbacher

John Brink, 1837 1975, L. Gerschbacher, RLS #18990  
Cross Indian Reserve Line SET ~~1/4"~~ 3/4" x 18" Iron Bar, ~~replaced~~ w/ 1 1/2" Iron Pipe  
@ 40.57 chains #3 Power Pole S35°W 140.62' FOUND cont., Found Existing Iron  
#4 Cherry S04°W 109.85'  
#5 Cherry 12" S75°E 58.55' #7 Cherry 12" S75°E 57.74'  
#6 Red Pine 8" N58°W 98.20' #8 Red pine 8" N58°W 98.46'  
1902, Harrison Knight Monument not given- Book "B", pg. 96  
#1 W. Pine Stump 20" S52 1/2°W 201ks.(13.20') 1988, K. Ross, RLS #17834 East 1/4 Cor. South 38.28'  
#2 W. Pine Stump 18" S 57°E 571ks.(37.62') cont.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

M-08 I Indian Reserve Corner, T22N, R16W, on East Township Line

On May 6, 1996, I found 5/8" Iron Rod w/ RLS Cap # 18990, below the Rod I also found 1 1/2" Iron Pipe. There still <sup>is</sup> existing old fence running to ~~the~~ East, I found no evidence to disputed this location for the corner.

Condition of recorded witnesses are;

- #1 Gone
- #2 Gone
- #3 Found in good condition
- #4 Gone
- #5 Found in good conditon
- #6 Found in poor condition
- #7 Same as 5
- #8 Same as 6

ratified by the Manistee County Peer Group according to the county plan adopted pursuant to P.A. 345 of 1990 as amended, (being the State Survey and Remonument Act, MCL 54.28) Date of Peer Review: JUL 1 1996  
*Anthony M. Slawinski*

C. Description of monument for corner and accessories established to ~~reestablish~~ locating the position of the corner:

M-08 I Indian Reserve Corner, T22N, R16W, on the Township Line

I repaced both existing Irons, in the exact location with a Standard Manistee County Monument, set 1 foot below the road surface, and is accepted as a careful and faithful reestablishment of the position of the original corner.

- (OBT #5) Wild Cherry 20" S 75° E 57.74' (60d spike in NE side of tree)
- Cut-off Power pole N 60° E 34.62' (60d spike in NW side of Pole)
- Red Pine 10" S 38° W 110.88' (60d spike in NW side of tree)
- Red Pine 11" N 65° W 101.85' (60d spike in NE side of tree)



Signed by *Sammy S. Barnett* Date 6-26-96  
Surveyor's Michigan License No. 16923