

LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

FOR CORNERS OF--:	LOCATED IN--:	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY _____ T. <u>23</u> N. <u>13</u> W.	•, R. <u>13</u> W.	B-1; C-1
2. PROPERTY CONTROLLING IN SECTION <u>6</u> T. <u>23</u> N. <u>13</u> W.	•, R. <u>13</u> W.	Code 1
3. MISCELLANEOUS PROPERTY IN SECTION _____ T. _____ S. R. _____ E. W.		
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, Carl F. Rober do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above (identified with circles on index code diagram—over) were, in a field survey on 1-9 1973, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on _____ 19____, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. Description of original monument and accessories and/or subsequent restoration:

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

- B-1** Accepted nail in center of E-W blacktop road, in line with fence to North as proper corner.
- C-1** Found RR spike in center of N-S blacktop road in line with fence East. Old accepted corner of record.
- Code 1** Established corner per standard B.L.M. instructions.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

B-1	C-1	Code 1
Set 3/4"x12" Boat Spike	Drove B.Spk along side RR Spk.	Drove B.Spk in Approx Ctr.
P.Pole Due S 37.33'	9" Cedar N42W 47.8'	E-W road
14" Maple S72W 103.95'	5" Tw Poplar S59W 37.8'	16" Hemlock N56W 103.9'
P.Pole N57W 59.52'	5" Cedar N89E 28.7'	20" Hemlock N20W 93.4'
Set loc tag on fn.	Set loc tac on cor. fn	4" Cedar S55E 74.7'
post Due N 33'	post Due E 33.4'	Set Ced post w/loc tag Due S 33'
Fd. 3/4" pipe S 36.5'		


SIGNED BY Carl F. Rober DATE 6-15-73

SURVEYOR'S MICHIGAN REGISTRATION NO. 12028

FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY _____ DATE _____
CHIEF OF SURVEY PARTY

APPROVED AND SIGNED BY _____
MICHIGAN REGISTERED LAND SURVEYOR



SURVEYOR'S MICHIGAN REGISTRATION NO. _____