

LAND CORNER RECORDATION CERTIFICATE
FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

FOR CORNERS OF-- LOCATED IN-- CORNER CODE NUMBER
1. PUBLIC LAND SURVEY T. 23 N. 13 W. B-2; B-3; C-2; C-3
2. PROPERTY CONTROLLING IN SECTION T. N. S. R. E. W.
3. MISCELLANEOUS PROPERTY IN SECTION T. N. S. R. E. W.
4. LOT NO. , RECORDED PLAT
5. PRIVATE CLAIMS

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, Carl F. Roser do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above (identified with circles on index code diagram - over) were, in a field survey on 1-8 1973, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on 19__ , found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. Description of original monument and accessories and/or subsequent restoration:

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:
B-2 Accepted King post, Ced. Fn post with fence remains N-S-E, Ctr of Sec. as occupied. Corner fits extremely close to computed ctr. of Section.

B-3 Recovered bottom of fence post in line with fn. to N & W. Same corner as accepted and used by J.H. Millard in Jan. 1900. See Co. Sur. Book at Register of Deeds.

C-2 Restored corner at proportionate mea. between Sec. cors. N&S (not on line) and in ctr. of N-S B.Top Rd. which fits fn remains W and 1/8 line fence 1/4 mile N. Also see old Co. Surveys of record at REG of Deeds.

C-3 Restored cor in ctr of N-S B.Top Rd in line w/fn remains E&W which fits cors. & Occupancy 1 mile N & S and old surveys of record at Reg. of Deeds.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
B-2 Set 1"x36" pipe by King post. Nailed Loc.tag on post. 6" Cherry N39E 63.4'. 5" Cherry N62E 68.8'.
C-2 Set 1"x18" pipe. P.P. w/transformer N27E 179.82'. P.P. S15E 251.45'. Ced.post & loc.tag Due W 33'.
C-3 Set 1"x18" pipe. 12" Maple S57E 49.7' (4-cluster). 8" Ironwd S21E 98.5'. 4" J.Pine S47W 69.4'. Set Ced Post w/loc tag Due E 33'. Ctr dirt Rd West Due S 18'.

B-3 Set DNR Mon 7 Ced Gd post by old cor.post bottom. 28" Maple S22E 60.88'. 9" Maple S75E 156.63'. (5-cluster) SIGNED BY

Carl F. Roser DATE 6-15-73


SURVEYOR'S MICHIGAN REGISTRATION NO. 12028

FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY CHIEF OF SURVEY PARTY

DATE

APPROVED AND SIGNED BY MICHIGAN REGISTERED LAND SURVEYOR



SURVEYOR'S MICHIGAN REGISTRATION NO.