

LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

MANISTEE

(County)

Located In:

Corner Code #

1. Public Land Survey

T 23 N R 14 W

M-9

T 23 N R 13 W

A-9

T R

T R

2. Property Controlling in Section

S T R

S T R

3. Miscellaneous Property in Sec.

S T R

S T R

4. Lot No. _____, Recorded Plat _____

5. Private Claims _____

I, Sammy S. Barnett, in a field survey on June 14th 19 99, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

M - 9 Corner common to sections 24 & 25 T23N, R14W & sections 19 & 30 T23N, R13W

1838 GLO survey by John Brink, set post
1 Sugar 11" S59W 16 lks (10.56')
2 Beech 14" N5W 50 lks (33.0')

1986 survey by A.M. Slawinski, found 1" I.R.
3 Tw. R. Oak 22" N70W 53.70'
4 Maple 14" North 39.22'
5 W. Pine 4" S30W 50.22'
6 C/L blacktop South 5.2.
7 Spike S45W 2.82'

SURVEY & REMONUMENTATION

DEC 09 1999

SECTION

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

M - 9 Corner common to sections 24 & 25 T23N, R14W & sections 19 & 30 T23N, R13W

On July 7th 1999, I found the 1" Iron Rod, the condition of the witnesses are as follows, Gone # 1, # 2, # 3 & # 7, found in good condition # 4, # 5, & # 6.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

M - 9 Corner common to sections 24 & 25 T23N, R14W & sections 19 & 30 T23N, R13W

On July 7th 1999, I replaced, in the exact location the found 1" iron with a standard Manistee mon., stamped to identify the corner, in a monument box and accepted this location as the best available evidence of the position of the original corner, and took the following witnesses.

4 Maple 16" N02W 39.12' fd. nail, set 60d spike in E. side
5 W. Pine 6" S30W 50.17' fd. nail set 60d spike in SW side
6 centerline of blacktop road S. 5.2'
7 W. Cherry 4" S31E 47.05' set 60d spike in NE side
8 W. Pine 4" S60W 75.03' set 60d spike in NW side
9 Power pole N70W 127.60' set 60d spike in SW side

Corner M-09

verified by the Manistee County Peer Group according to the county plan adopted pursuant to F.A. 315 of 1990, as amended, (being the State Survey and Remonument Act, MCL 54.201 et. seq.). Date of Peer Review:

Anthony M. Slawinski

AUG 03 1999

Signed by Sammy S. Barnett

Date 8/1/99

Surveyor's Michigan License No. PS # 16923

REGISTER'S OFFICE
MANISTEE COUNTY

99-251 at 4:15pm
AUG 12 1999

Rebimah Dix
REGISTER OF DEEDS

Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													