

Common corner  
w/ L-13  
T 23N R 13W

SURVEY &  
RECORDATION

MAY 03 2000

**LAND CORNER RECORDATION CERTIFICATE**  
Filing Requirement of Act 74, Mich. P.A. 1970

SECTION

For corners in

<u>Manistee</u> (County)	Located in:	Corner Code #
1. Public Land Survey	T <u>24N</u> R <u>13W</u>	<u>L-13</u>
	T _____ R _____	<u>South ¼ Cor.</u>
	T _____ R _____	<u>Sec. 36</u>
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

**REGISTER'S OFFICE**  
**MANISTEE COUNTY**  
99-226 at 1:40pm  
**JUL 22 1999**  
*Deborah Six*  
**REGISTER OF DEEDS**

Register of Deeds Stamp & File  
Number

I, Anthony M. Slawinski, in a field survey on June 4, 1999 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	13		17		16		15		14		12		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

**NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.**

A. Description of original monument and accessories and/or subsequent restoration:  
L-13 South ¼ Corner Section 36 T24N, R13W

Set by John Brink in 1838

1. Elm 6" dia. N 53° W 0.5 links (0.33') (Gone)
2. Lynn 6" dia. N 52° W 30 links (19.8') (Gone)

Survey Certificate by Zwar, 1996  
Found ½" Iron Rod

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:  
L-13 South ¼ Corner Section 36 T24N, R13W

On June 4, 1999, I Anthony Slawinski, with a field crew from Abonmarche found a 12" cabin spike in a monument box. I found no other evidence to dispute this location for the corner.

Corner L-13 ratified by the Manistee County Peer Group according to the county plan adopted pursuant to P.A. 345 of 1990, as amended, (being the State Survey and Remonument Act, MCL 54.261 et. seq.) . Date of Peer Review: *Anthony M. Slawinski*  
JUL 6 1999

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:  
L-13 South ¼ Corner Section 36 T24N, R13W

On June 4, 1999, I set a Manistee County Monument, within a monument box in the exact location of the above mentioned cabin spike as a careful and faithful re-establishment of the position of the original corner and witnessed by:

3. N 33° W 25.71' Guard Rail Post (Set 60d spike in the West side)
4. N 38° E 26.24' Guard Rail Post (Set 60d spike in the East side)
5. S 41° E 22.96' Guard Rail Post (Set 60d spike in the East side)
6. S 35° W 18.04' Guard Rail Post (Set 60d spike in the West side)

Note: The corner is in the centerline of 13 Mile Rd.



Signed by *Anthony M. Slawinski*  
Surveyor's Michigan License No. 13597

Date 7-2-99