

LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

FOR CORNERS OF--	LOCATED IN--	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY _____	T. <u>23N</u> N. <u>13W</u> E. _____ S., R. _____ W.	M13
2. PROPERTY CONTROLLING IN SECTION _____	, T. _____ N. _____ E. _____ S., R. _____ W.	
3. MISCELLANEOUS PROPERTY IN SECTION _____	, T. _____ N. _____ E. _____ S., R. _____ W.	
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER'S OFFICE
MANISTEE COUNTY
 #94-244 AT 9:45
JUN 15 1994

Penney G. Pepera
 REGISTER OF DEEDS

REGISTER OF DEEDS STAMP AND FILING NUMBER

SURVEY & REMONUMENTATION

JUL 14 1994

COMMISSION

I, Patrick R. Leemon do hereby certify that under requirements of P.A. 74, Michigan P.A. of 19 the corner points mentioned in lines 1 and 2 above (identified with circles on index code diagram - over) were, in a field survey on March 30 1994, established, re-established, monumented, re-monumented, recovered, restored as expressed below and in conformance with regulations and rules therefore as required in the current map of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey _____ 19____, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. Description of original monument and accessories and/or subsequent restoration:

Section corner common to section 36 of T23N R13W, section 31 of T23N R12W, section 1 of T22N R13W and section 6 of T22N R12W

- | | | |
|--|--|--|
| <p>1838 survey by John Brink
 Set Wood Post
 #1 W.Pine 16 S56 1/2 W 35 links
 #2 W.Pine 11 N31 1/2 W 21 links</p> <p>1908 survey by E.H. Baird
 Fd. GLO old stake & Bearing Trees
 #3 W.Oak 14 N41W 23 links
 #4 W.Pine 12 S20E 15.5 links</p> | <p>1909 survey by Fargo Eng.
 Fd. GLO stake & set I.P. w/ lime
 #5 W.Pine Stp. 18 N1W 89 links
 #6 W.Oak 16 S70 1/2 E 2.33 chains
 1985 survey by Ed McCombs
 #10696 Fd. conc. monu. by Griffin
 #12 Oak 6 N32E 33.80 feet
 #13 Pine 8 N48W 58.43 feet
 Also used wit's. #8 and #9</p> | <p style="text-align: right;">#13584</p> <p>1966 survey by Robert A. Griffin
 Fd. lime a Wit. # 6. Iron is gone.
 replaced w/ a 5" sq. x 36" long
 conc. monu. w/brass cap
 #7 R.Pine 6 N45E 77.86 feet
 #8 W.Oak 7 S44E 65.77 feet
 #9 W.Oak 10 S43W 70.32 feet
 #10 R.Pine 4 N67W 58.66 feet
 #11 Cedar Post West 33 feet</p> |
|--|--|--|

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

I found the 5" square by 36" long concrete monument w/ brass cap by Griffin buried 12" beneath the surface, in the centerline of the N-S road and 3 feet south of the centerline of the road to the east. Witnesses 1 through 6 and 11 through 13 are gone. Witnesses 7 through 10 are in good condition. This monument was used in a 1990 survey by Clinton Cole #17615. This monument is accepted as a careful and faithful perpetuation of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Section corner common to section 36 of T23N R13W, section 31 of T23N R12W, section 1 of T22N R13W and section 6 of T22N R12W

Monu. The 5" sq. by 36" long concrete monu. with 3" brass disk was left in place.

- Witnesses:
- R.Pine 9 N45E 77.86 feet (#7)
 - W.Oak 9 S44E 65.77 feet (#8)
 - W.Oak 12 S43W 70.32 feet (#9)
 - R.Pine 4 N67W 58.66 feet (#10)


SIGNED BY *Patrick R. Leemon* DATE April 20 1994

SURVEYOR'S MICHIGAN REGISTRATION NO. 31595

FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY _____ DATE _____
CHIEF OF SURVEY PARTY

APPROVED AND SIGNED BY _____ DATE _____
MICHIGAN REGISTERED LAND SURVEYOR



SURVEYOR'S MICHIGAN REGISTRATION NO. _____

Corner 1 - 13
 ratified by the Manistee County Peer Group
 according to the county plan adopted pursuant to P.A. 345 of 1990,
 as amended, (being the State Survey and Reestablishment Act MCL 207.1203)