

MICHIGAN
DEPARTMENT OF CONSERVATION
FORESTRY DIVISION

LAND CORNER RECORD

T. 23. NR. 14 W.
24 14W

Manistee COUNTY

DESCRIPTION OF CORNER Closing Corner common to Sections 2 and 3
on North Boundary of township

DESCRIPTION OF CORNER MONUMENT 1" pipe with 4" brass cap

WITNESSES TO CORNER

7" Cedar - S85W - 30 links
8" Cedar - S22E - 6 links

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

This corner was found by Forestry Division survey crew while making a survey in T24NR14W. Found old stake at corner and 2 NBTs, probably as established by Manchester in early 1900s. B. Ash governments BTs gone but corner is correctly related to standard corner and appears acceptable as best available evidence.

Corner to Sections 34 and 35, T24NR14W is 30 links east.

Corner was set and witnessed January 7, 1960.

SURVEYORS SEAL

SIGNED Kenneth J. Estlin DATE 1/5/60
REGISTERED LAND SURVEYOR