

MANISTEE COUNTY
LAND CORNER RECORDATION CERTIFICATE
FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

FOR CORNERS OF--	LOCATED IN--	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY	T. 23 N. 14 W.	L-3
2. PROPERTY CONTROLLING IN SECTION	12 1/2, T. 23 N. 14 W.	(SEC. 12) (SEC. 1) Code 7; 15; 16
3. MISCELLANEOUS PROPERTY IN SECTION	T. N. E. S. R. W.	
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, Carl F. Roser do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above (identified with circles on index code diagram - over) were, in a field survey on 1-8 1973, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on _____ 19____, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. Description of original monument and accessories and/or subsequent restoration:

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:
L-3 Recovered stake - Manchester corner of record. Fits corner by single proportion.

SEC. 12 Code 7 Established corner per standard B.L.M. instructions.

" 15 Recovered Manchester corner of record. Fits corner by single proportion.

SEC. 1 " 16 Recovered 4"x4"x18" sq. wood stake which fits 1/16 corner by single proportion.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner.

L-3	Code 7 SEC. 12	Code 16 SEC. 1
Fd 4"x4" stk. Added DNR Mon & Ced Gd. Post	Set 1"x36" pipe & Ced Gd Post w/loc tag	Fd 4"x4" Stake. Added 1"x36" pipe & Ced. Gd Post w/loc tag
30" W. Pine stp N 5E 38.4'	6" Cedar N57W 33.3'	7" Cedar N42W 20.1'
5" tw Hemlock S67W 22.7'	4" Cedar N16W 49.4'	6" Cedar S 4W 9.4'
4" tw Hemlock S 1E 33.0'	4" Cedar N87E 32.9'	14" Cedar stub
48" W. Pine stp N77W 75.0'		12' high S34W 35.0'
	Code 15 SEC. 1	
	Fd 1 1/2"x60" pipe in E-W fn. Added 1"x36" pipe & loc. tag	
	12" Maple S61E 43.3'	
	12" Maple S67W 67.0'	
	4" " triple N32W 14.3'	


SIGNED BY Carl F. Roser DATE 6-15-73

SURVEYOR'S MICHIGAN REGISTRATION NO. 12028

FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY _____ DATE _____
CHIEF OF SURVEY PARTY

APPROVED AND SIGNED BY _____ DATE _____
MICHIGAN REGISTERED LAND SURVEYOR



SURVEYOR'S MICHIGAN REGISTRATION NO. _____